

July 17th 1891

Standard measure on 2nd Street between
monuments on Lincoln and Hall avenues

Standard 200' steel tape 16 lbs tension 68°F

1st measure Westward on slope 765.01

Temperature 104°

Slope 0.06

B42

2nd measure Eastward on slope 764.99

Temperature 104°

Slope 0.06

Measure	765.01
Correction 36°	0.187 ✓
	<hr/>
Slope 0.06	765.197
	<hr/>
	765.196

Corrected for slope & temp = 765.196

B42

Measure	764.99
Correction 36° temp	0.187
	<hr/>
Slope 0.06	765.167
	<hr/>
	765.166

Corrected for slope & temp 765.166

196
567
181