

July 14th 1891.

Standard measure on 24th sheet between
monuments on board & Swedish monument

Standard 200' steel tape. 16 lbs tension

68° 8'

1st measure westward on slope 765.88

Temperature 110°

Slope 0° 11'

B42

2nd measure eastward on slope 765.88

Temperature 110°

Slope 0° 11'

Measured dist 765.88

Temp. Cor 0.19

766.077

Slope 0.04

766.095

Corrected for slope & temp 766.095

B42

Same as above