

This task and measure angle from
Court House spire to chimney of
Sturms house, mean of 4 repeated
readings checks exactly, viz. $69^{\circ}19'$
I therefore adopt this task as the
true location of Sec. center.

From Court House spire I turn left
and south by old note $25^{\circ}18'$ and set
flag pole about 10' west of section center
on line running to 40 but 33 + 24
to use hereafter as a F.P.

Retraced to 40 but 33 + 24 and read
angle between Eyrie PK and flag pole
set 10' west of center Sec. 33,
Mean of 5 repeated readings give $73^{\circ}59'$
instead of $74^{\circ}00'$ as record gives it.

I then turned
proper angle for N.E. cor. Sec 33
and made search for corner but
failed to find one as it was