

Survey for Mt at center
of 29th St. & Grant Ave.

July. 15, 1892 - p. m.

Set for Fore-sight the intersection
0.005 ft. West of Mt. at Wash. Ave and 25th
St, which point is correctly on
the adjusted standard alignment
of Wash. Ave.

Set Surt, 0.099 ft. east of Mt at
Wash. + 29th St, which point
is also on the adjusted
standard alignment of Wash.
Ave.

On account of obstructions to
the west I line in hub
34.84 feet north of Mt. 29th + Wash.
Ave. and on Standard Line from
which to right-angle to the
west down 29th St.

Set up on this latter hub
and with F.O. as before repeated
right angle to west down