

29th St., 10 times and set
hub + look for intersection on
either side of center line of
Grant Ave.

July 16. continued.

Set heliotope 0.077 ft. west of mt.
at 21st St. + Grant Ave., for
a B.S. same being on standard
alignment of Grant Ave for
producing surveys of same

Set transit 0.235 ft. east of mt.,
at 28th and Grant also on
standard alignment.

Produced Grant Ave standard
line by repeated double center
to intersection of hubs on 29th
St. said intersection being on
center of Grant Ave and
34.82 ft. north of center of
29th St.