

Survey locating Post Corners  
Grant Ave bet 22<sup>d</sup> + 23<sup>d</sup>  
New School Building -  
Grade Nth

Description of property -

The North half of Lot No 1  
in Block No 38 - Plat A

Measured between monuments  
at 23<sup>d</sup> + 22<sup>d</sup> twice and found  
distance 761.420 + 761.425, mean 761.42  
I therefor locate point at center for  
North line of lot - I then measure  
165.6 feet South and set point -  
Turn West 90° and set hubs 49.5 + 182.9  
from center - Thus fixing lot lines -  
Put no stake at N.W. cor. on acct  
of obstructions -

I then measure North from S. line  
81 feet and set point in center of  
Grant - Thence set points 90° West 72.9  
and 172.9 - Thence Transit at these  
points I turn 90° and set hubs as  
shown - as directed by N.W. Hunscomb