

Setting of Grades for  
Paper Laying,

(See p. 11)

Sta	R.D.	H.L.	F.D.	Elw.	Grade	Cut.
0	12.59	12.59		0.00	0.00	
0			3.59	9.00	0.00	9.00
+30			3.59	9.00	0.50	8.50
+50			3.89	8.70	0.70	8.00
+75			3.64	8.95	0.95	8.00
1			3.89	8.70	1.20	7.50
+25			4.14	8.45	1.45	7.00
+50			4.89	7.70	1.70	6.00
+75			5.14	7.45	1.95	5.50
2.			5.39	7.20	2.20	5.00

Apr. 30. 1892

12

An Invert of 4" branch of Sewer.  
An grade stake at surface

From Sta 0. (at the Sewer 4)

to Sta 0+30, the grade

is purposely made .50

instead of @ a 1% grade

in order to give better

flow into the sewer

Grade boards and tight  
line furnished the work-  
men as usual on the  
sewer construction.