

Snowy & set hub - for
of 29th & Quincy -
May 7/92

Monument at corner

13

Heliotrope at monument
on corner Quincy & 29th
and sight at Quincy & 28th
and transit near " & 29th
line in transit and

set two hubs on center line
of Quincy where line
42.5 South of center of
29th would intersect
(This line having been
previously established) -

Then determine intersection
of these two lines - and
measure 42.5 North
and set 2" x 2" x 8" hub
for proper location
of monument