

Line of stakes for changing
North fence line of city
Cemetery to a parallel
line with 20th Street -

Transit at Hub A (= intersection Adams + 20th)

I project center line Adams to point
"E" on line parallel with 20th Street
through C (= N.W. corner of cemetery as
indicated by present fence lines)

The distance from A to E being 577.4.

I go to F (= intersection 20th + Madison)
and finding no hub I measure
from B (= Monument at 21st + Madison)
759 feet north to F - and then
with 577.4 to point D.

Then with foresights at C and
transit at D - I run a line of
1" x 2 1/2" stakes between A & C about
200 feet apart -

