

(Continued)

Beginning at center of
 Sec 34 and running south -
 S. 4 corner - on an azimuth of $0^{\circ} 45\frac{1}{2}$
 (This pointing to fence & pole that I
 supposed to be on the corner)

	Slope Measure	Int. Angle	Length of Sighting	Temp. red	Cor. slope
Main	20011	- 1 ⁰⁰ 9	100	88°	-.04
"	50041	- 4 ⁴⁸	500	86°	-1.76
"	50041	- 0 ⁵²	200	82°	-.05
"	50041	- 0 ⁴⁴	100	88-86	-.04
Steel Tape	100	- 0 ⁰⁰	-	81	
"	50041	+ 2 ²²	500	78-84	-.42
"	35019	- 0 ⁵⁴	350	82-76	-.04
	2651.94			79	

True Hor. Dist.	rections		
	Cor.	Temp.	Total
200.08	-.01	+0.02	-.03
498.17	-.52	+0.04	2.24
500.36	-.03	+0.03	-.05
500.42	-.01	+0.06	+0.01
100.00			
499.49	-.52	+0.02	-.92
349.98	-.17		-.21
2648.50			3.44

Main standard at 78°
 Tape " " 78°

From this latter point I turn 90° 00'
 East and measure 31.15 to pile
 of half dozen boulders about 6" in
 diameter - in midst of patch
 of ^{low} scrub brush which I regard
 as marking the corner -
 There are no fences or lines
 of any kind to indicate loca-
 tion of this corner - I made

inquiry of man owning land here and
 he says that the corner is on the same
 line at a point about 50 feet further
 south and is marked by a cedar stake - this
 is in scrub, matted brush - and a search
 failed to reveal any evidence whatever
 of the Cor. I should claim the corner was
 near the bushes 15 years ago -