

Cemetery lot

Survey to determine if certain
stakes purporting to be the
corners of Lot 12 Block 4
of River View addn. etc.
May 26th

Back sight to monument corner of
Wall + 28th Just at monument
Cor Pacific + 28th Both on 1 foot
offset North -

I measure West 718.2 ft -

Thence turn 90° South and measure 600 ft

Thence 90° West and measure 23 feet

Thence 90° South and " 34.5 ft to stake

Marking S.W. Cor. of South lot 12 -

Then crossing in altitude I measure
53.5 from this stake and upon search
find base of old tub in ground -

(top has been broken off)

Thence turn 90° East and measure
143 feet and set transit at this
point -

Thence 90° South + measure 35.0 to hub

Marking S.E. Cor. of lot -

Thence crossing in altitude I measure
53.5 feet North from this last

Hub to Hub at N.E. Cor - Thus checking the lot location - finding it OK.

Note: Incidentally I
measured from stake I found on
West Alley line of Block 3 at 28th
Street - viz the N.E. corner of lot
No 1 Block 3 - North to our
line on one foot offset
North of monuments on 28th
St - and found the
Distance to be 27.5 feet