

174.24
435.60

36

B.P. to point just left.
(N.E. cor. $N\ N^{\circ} N\ E^{\circ}$ Sec. 8)
reverse + continue, setting
hub 375' south of N.E. cor
 $N\ N^{\circ} N\ E^{\circ}$ Sec. 8. which I think
will be the N.E. cor. of
the Groome tract.

Continuing south 500'
further viz. 875' south
of the N.E. cor $N\ N^{\circ} N\ E^{\circ}$ Sec. 8.
set hub for S.E. cor. of
the Groome tract.

Sitting on each of these
latter two hubs, with F.O. to
northward on line just
run I angle 90° west
and set stakes at
distances, 174.24' and
435.60' respectively thus
completing the survey
of a 3 acre and a
2 acre tract adjoining
each other.

60