

Survey for Extension of City

Cemetery Mar 21<sup>st</sup> 1895

STA.	ANGLE		CAL. COURS. MAG. C.
	L	R	
0 P.			N0°58'E
14+67.5 P.	90°00'		N89°02'W
28+50 P.	35°16' L		S55°42'W
30+38.25 P.		29°48'	S85°30'W
32+45			corner of fence

STA 13+06.5 Intersection point of north side of lots with center of Madison ave.

Set up one monument at 21<sup>st</sup> & 4<sup>th</sup> Madison backsighted on monument at 22<sup>nd</sup> & 4<sup>th</sup> Madison. Assumed that center of 21<sup>st</sup> street was station 0 and that sta. 14+67.5 was north side of 19<sup>th</sup> or North st. Set joint at sta. 14+67.5 and turned angle of 90°00' to left and produced this line to sta. 28+50. This line being on an offset of 100 ft. to the south.

At station 23+88 the edge of bluff is 100 ft north of offset line, at sta. 25+25 edge of bluff is 15 ft north of offset line. Sta. 26+50 is on edge of bluff and meander line runs along edge of bluff from there to N.W. corner of present cemetery 869.6 ft from west side of Madison ave. to first angle in fence.

