

Dec. 6-1895,

Field notes, of survey of Wilson Irrigating Canal as connected with the centre of the street running N. N. from the Weber Bridge at N. end of 24th St. Survey begins at Co. Mount N^o 61. (See page 49)

At Co. Mount N^o 61, I. turn off from Exier Peak on angle of 65° 03' from N. to E. and run S 72° 58' E. along center of St.

- 717.
- 100 N. edge of Wilson canal S. 20 ft dist. called 12 ft
 - 200. N. Edge of canal S 37 ft dist. canal 13 ft wide
 - 227. N. edge of stone culvert where canal passes under H. C. Ry track bears S 17° W. 79 ft dist. Culvert 13 ft wide.

At County Mount N^o 61. I turn off from Exier Peak on angle of 91° 59' from N. to W. and run N 50° 00' W. along the center of the street.

- 70 N. E. end of wagon bridge over Wilson canal bears S 20° 03' W. 39.5 ft dist. span of bridge 20 ft width of bridge 21 ft.
- 100 N. edge of canal bears S 38 ft
- 200 N. Edge of canal bears S 40° W. 44 ft dist
- 300 N. edge of canal S 40° W. 36 ft dist wire fence bears N 40° E 59 ft dist

Ft

- 400. N. Edge Canal bears S 40° W 25 ft wire fence N. 45° E 43 ft dist.
- 500 N. Edge canal S 40° W 31 ft dist wire fence N 40° E 55 ft dist
- 600 N. Edge of canal S 40° W 37 ft dist wire fence N 40° E. 50 ft dist
- 648.3 wire fence N 40° E. 45 ft dist
- N. Edge canal S 40° W. 42.5 ft dist

Thence I turn

N. 55° W.

- 100 N. Edge of canal S. at right angles to center of road 40 ft dist wire fence N. R.A. 25 ft dist
 - 200 N. Edge of canal S. (at r.a.) 45 ft dist wire fence N. at r.a. 42 ft dist.
 - 300 N. edge canal S. (at r.a.) 45 ft dist wire fence N. (at r.a.) 35.5 ft dist
 - 400 N. edge of canal S. (at r.a.) 43 ft dist. wire fence N. at r.a. 20 ft dist.
- On a point entering branch I turn on angle of 90° from N. to S. and offset ~~15~~ ¹⁶ ft measure 15 ft for an offset line & thence I turn N 55° W.

On an offset 15 ft S. of center of street

- 33 N. end of wagon bridge over canal South 27 ft dist S. edge of branch North 10 ft dist