

Survey of 1/2^{mi} East from Washington
Colo. Nov. 21, 1896

see page 75

76

Description of a county road 4 rods wide
leading from the Mound Fort School House in Ogden
City Eastward to Fair Woolen Factory. Thence
down Ogden Valley Road to city limits

Beginning in the center of Main St.
at what is known and described as County Survey
Monument No 3, situated 187 ch (120.12 ft) $N 54^{\circ} 16' 11''$
from N.W. corner of the Mound Fort School House,
with bearings to Benlomon Peak $N 2^{\circ} 44' 2'' E$
and to Observatory Peak $S 56^{\circ} 53' 2'' E$, running thence
thence $S 50^{\circ} 45' E$ 10.06 ch (663.96 ft) intersecting
the road from Ogden City to Ogden Valley at
Monument No 90 situated 9.44 ch (623.04 ft)
North and 2.62 ch (172.92 ft) east from the S.W.
corner of the N.W. 1/4 of Sec. 22 T.P. 6 N. R. 1 W. S. L. M.

The bearing from said monument being to
Benlomon Peak $S 5^{\circ} 12' W$, to Observatory Peak
 $S 49^{\circ} 39' E$ and to the N.E. corner of the main building
of the Woolen Factory $S 39^{\circ} 22' W$ 2.06 ch (135.96 ft). Said
road being 95.2 ch (6283.2 ft) in length from its beginning
to this point. Thence continuing in the center of said
road $S 64^{\circ} 46' E$ 32 ch (2112 ft) thence $S 79^{\circ} 30' E$ 27.56 ch (1816.4 ft)
thence $N 83^{\circ} 45' E$ 14.64 ch (966.24 ft) thence $S 52^{\circ} E$ 13.24 ch
(873.84 ft) thence $S 17^{\circ} E$ 8.16 ch (538.56 ft) thence $S 39^{\circ} 30' E$
4.60 ch (303.6 ft) thence east

of the street
following the center