

No. Hole	Dist. Paces	Remarks		
#32 1	55	6" pipe 3 pits close together Soil sandy clay damp	on top -	20%
#33 2	102	6" pipe - small pits not Soil black + sandy - wet	fully developed	33%
#34 3	203	6" pipe - good condition Soil gravelly very dry.		10%
#35 3 1/2	262	6" pipe some large pits - Soil clay		20%
#36 3 1/2	328	6" pipe joint <sup>and</sup> connection much rust, a few large and Soil moist clay	to 2358 Lincoln joint leaking slightly many small pits 1/16 in deep about	75%
#37 5	414	6" pipe - a few rust pits " " " Soil clay - not much moisture	caused by corrosion probably in pipe when laid - pipe not condition	"Rust" "Banded" 10%
#38 6	479	6" pipe - very much rust - many more. Soil adobe clay damp	large and small pits - deep - over 1/16 in	50% or more
#39 7	572	6" pipe - good condition	coating not injured - Soil, surface brown	10%
#40 7 1/2	562	6" pipe - 10 pits in 2 ft in length	33% soil sandy clay	
#41 8	637	6" pipe - joint slight leak about 15%	pitted about joint. coating has been pitted some - Soil medium dry clay	
#42 8 1/2	784	6" pipe - fair condition - 3 small Soil - clay brown	pits	10%