

Washington Ave. North from 25th St. Pipe LineNo. of hole
Diect.
Feet.

#55	1	50	12" Pipe - two connections & pipe good.	Rust and pits around connections - rest of	10%
#56	2	381	12" Pipe. a few small pits covered shows poor condition. Soil sandy clay - damp	otherwise in good condition - joint not un- from the dampness of surrounding soil	10%
#57	3	453	12" Pipe - In good condition Soil - Wet Clay		10%
#58	4	579	12" Pipe connection to # pipe - No Examination on account 25% deterioration	Wash ave - connection broken off in uncovering of water - until after repaired - when about was found - several deep pits	
#59	5	753	12" pipe - about a dozen small pits Soil - Loam - dry -	shallow pits	20 to 25%
#60	6	860	12" Pipe one rust spot 3" long especially on bottom of pipe	1" wide over 1/16" deep - Many small rust spots	20%
#61	7	1081	12" pipe - at joint in fair condition Soil Gravelly loam - dry	pipe also in good condition	15%
#62	8	1219	12" pipe - In good condition Soil Gravel dry		10%