

#105 ✓

Washington Ave 200ft N of 27th St. 12" pipe

at joint - much rust - pitted but not deep
very numerous - 50%
Soil dry loam

#106 ✓

Wash. Ave 100ft S of 26th St. 12" pipe - At joint

"waterworks man just recaulked joint"
four very bad pits. some rust
Soil wet clay 50%

#107 ✓

Wash. Ave 100 ft S. of 27th St. 12" pipe - at con.

nection to # many pits - much rust 50%
Soil wet clay
"Examination was after Mr. Kercher left"

#108 ✓

Wash. Ave 300ft S of 27th St. 12" pipe - at joint

same having been recaulked just before
Examination - very much rust & badly pitted
50% Soil sandy loam dry

#109 ✓

Wash. Ave 100ft N of 28th St. 12" pipe - at joint

Slight leakage at joint - thickly covered with
small deep pits. Soil wet clay 50%

#110 ✓

Wash. Ave 135ft S. of 28th St. 12" pipe - very

little rust - pits not developed 10 to 15%
Soil wet sand and clay

#111 ✓

Wash. Ave 470ft S of 28th St. 12" pipe -

Rust and pits numerous - Soil wet loam 50%

#112 ✓

Wash. Ave 806ft. S of 28th St. 12" pipe - at joint -

Much rust. numerous pits - 50%
Soil wet loam.

#113 ✓

Wash. Ave 1280ft S of 28th St. 12" pipe - very

little rust. and pits 30%
Soil damp clay and loam