

#114 ✓

Adams Ave 300 ft N of 28th St. 6" pipe -In good condition
old wooden pipe also uncovered at this
place - in good condition - Soil dry loam

47

#115 ✓

Adams Ave 35th S of 27th St. 6" pipe -In good condition - Soil dry loam -
old wooden pipe also in good condition

#116 ✓

27th St. 370 ft N of Grant Ave 6" pipe verymuch rust and many pits - 65 to 70%
some deep - Soil very wet clay. micaceous

#117 ✓

26th St. 250 ft N of Wash. Ave. 6" pipe - at joint

much rust and pitted - Soil wet loam 50%

old wooden pipe also uncovered at this place
firm and in good condition

#118 ✓

Wash. Ave 80 ft S. of 25th St. 12" pipe. not much

rust - some small pits 10% Soil gravelly loam

#119 ✓

Wash. Ave 75 ft N of 26th St. 12" pipe at joint -slight leak - pipe badly bent around joint and
slightly pitted - some rust - fair condition 20%
Soil Loam wet

#120 ✓

Wash. Ave 10 ft N of Patterson Ave 12" pipe - badly rusted

pitted Soil Loam 25%

#121 ✓

Wash. Ave 100 ft S. of 31st St. 10 in pipe - at jointslight leak - numerous pits. much rust 50%
Soil clay