

Survey for city. Apr 30, 1901
Opening of Wall ave
and 29th st

McDonaghe
Stoddard
Gentry

I met over mt. 15' N center 25th st + Wall
Back sight on mt 27th + Wall.
Turn 130° from N to S, + do not
intersect old hub at center of
29th + Wall set in 1890.

Set flag to center 25th + Wall.
Back sight + find the rule at 28th
27th + 25th to be on same tangent
I then turn 180° from N to S and
set intersection hubs at 29th
and 30th etc on Wall. D.C. in
each instance.

I met over mt. 29th + Wash.
Fore sight on mt 28th + Wash. Measure
37' N. and set nail. I met over nail.
Fore sight on mt 28th + Wash. Turn
 90° from N to W + set hub on W
side Lincoln ave. and also set
hub on W. side Pingree ave.

Then I offset above line 20' N. owing
to obstruction.

at Wall ave. set hub on line
with intersection hubs. Then
measured 17' S + set hub for
center 29th + Wall ave.

I met over mt. center Lincoln + 30th
Back sight on mt center Grant + 30th
Turn 180° from E to W + set intersec.
hubs at 30th + Wall. D.C.

Then set centre hub at pt
where two lines intersect.
From hub at centre Wall + 30th,
fence post on S.W. is dist. 63.4 and
fence post on N.W. is dist. 63.3.

I met over mt. 28th and Lincoln
Fore sight on center 30th + Lincoln

45 W. 20 S,

90°

60

