

Mar 18 1905

Survey to set 4 corners of Royal Avenue

Blk 48 Plat H.

Q.K.P. Int

D.O.F. chain

H.B. & chain

1 P.M. to 4:30 P.M.

Int over Int. 22<sup>nd</sup> & Lincoln F. & on Int. 22<sup>nd</sup> & Wall  
measure distance between monuments = 765.0 same

as recorded measure, no one will believe this but not  
judged. Measure West from Int. 22<sup>nd</sup> and Lincoln  
300.9 ft. = sta. 1 measure 32 ft. further = sta. 2. Int. over

sta. 1 F. & on Int. 22<sup>nd</sup> & Wall an. angle right and South 90° measure  
49.5 ft. set hub & tack = south end cor. Royal Ave. Int. over

sta. 2 F. & on Int. 22<sup>nd</sup> & Wall angle right and South 90°  
measure 49.5 ft. set nail in S.E. cor. <sup>point</sup> South West cor.  
Royal Ave. measure between hub & tack = 32 ft. chd.

Int. over Int. 21 and Lincoln F. & on Int. 21<sup>st</sup> & Wall  
measure 300.9 ft. set nail at sta. 1 measure 16 further at nail

= sta. 2 also center of Royal Ave. measure 16 ft. further  
set nail = sta. 3. Int. over sta. 1 F. & on Int.

21<sup>st</sup> & Wall angle left and South 90° measure 49.5  
ft. set hub & tack = N.E. cor. Royal Ave. Int.

over sta. 3 F. & on Int. 21<sup>st</sup> & Wall angle left and  
South 90° measure 49.5 set hub & tack = N.W. cor. Royal

Ave. Int. over sta. 2 F. & on Int. 21<sup>st</sup> & Wall angle  
left and South 90° set nail between hubs, at South

end ave. measure 15.94 ft. to hub at S.E. cor. of Ave,  
to chd distance should be 16 ft.

copied from Official Plat

