

Record of the County Court of Weber County, Utah Territory.

1885.

March 3.

In A. M. Court not pursuant to adjournment

Present: Hon. L. H. Shurtliff, Probate Judge,

Robert McQuinn, Esq.,

W. Montgomery, Esq., } Selectmen

E. C. Richards, County Clerk.

Prayer by Judge Shurtliff.

Minutes of yesterday were read and approved.

The Court concluded its labors in examining and comparing the boundaries and descriptions of roads returned by the Probate Judge and County Surveyor as having been surveyed or re-surveyed and located, under and in pursuance of an order of this Court duly made and entered on the 31st day of March, A. D. 1884; and after a full and careful consideration of the whole subject, the following resolutions were unanimously adopted, to-wit:

Resolved, That all orders heretofore made by this Court designating or declaring certain roads or streets to be County Roads or Highways be, and the same are hereby repealed and rescinded, to take effect immediately; and all roads or streets heretofore located as, or designated and declared by this Court to be, County Roads or Highways - except such as are hereinafter described and bounded in the minutes of the proceedings of this Court held this day - be, and the same are hereby discontinued, abolished and abandoned.

Resolved, That the roads and streets which are bounded and described as follows, be, and the same are hereby designated as, and declared to be, County Roads and Highways to-wit: ✓

Description of a County Road eight rods wide leading from Ogden City, Northward to the North line of Ogden City Corporation.

1. Beginning at a monument of sandstone in the center of what is known as Main Street Ogden 347 feet N. 87° 35' W from the center of the dome on the Weber County Court House, and N. 0° 25' E. 116 2/3 feet from the center of South Street - and running thence N. 0° 25' E. 80.76 chains to what is known and designated as "Weber County Survey Monument Number 2" situated in the center of a road leading Eastward - continuing thence N. 0° 25' E. 19.85 chains, to the quarter section line East and West through

Record of the County Court of Weber County, Utah Territory.

1885.

March 3.

Section 20, Township 6 North of Range One West - Salt Lake Meridian, and to "County Survey Monument No 4" thence $N. 0^{\circ} 15' E.$ 16.01 chains, to "Monument No. 3" situated in the center of streets leading East and West near the Mounds Fort School House thence $N. 0^{\circ} 15' E.$ 11.21 chains, to "Monument No. 5," situated in the center of a street leading Eastward thence continuing $N. 0^{\circ} 15' E.$ 11.26 chains, to "Monument No. 6" situated in the center of streets leading Eastward and Westward through "Lyons District," thence continuing $N. 0^{\circ} 15' E.$ 11.01 chains, to "Monument No. 7" situated in the center of a four rod street on the North boundary of "Ogden City Corporation" leading Eastward, being 20.72 chains $S. 0^{\circ} 15' N.$ and 10.50 ch West from the South East corner of the North East Quarter of Section Eight (8) Township Six North of Range One West Salt Lake Meridian - the bearing from said Monument No. 7 to "Observatory Peak" being $S. 115^{\circ} 21' E.$ The total length of said road is 240.10 chains.

Description of a road four rods wide, leading from Main Street in Lyons District near the residence of Robert Miller Eastward to the Mountain.

2. Beginning in the center of Main Street at what is known and designated as Weber County Survey Monument No 5 with bearings to DenLomond Peak $N. 2^{\circ} 54' E.$ and to Observatory Peak $S. 52^{\circ} 38' E.$ running from thence $S. 89^{\circ} 15' E.$ 117.12 chains, to Monument No 89 - The bearing from said monument to the United States Observatory, at Ogden being $S. 51^{\circ} 03' N.$ and to Observatory Peak $S. 41^{\circ} 49' E.$ and to the spire on the dome of the Weber County Court House $S. 35^{\circ} 38' N.$ From this point the said road continues $S. 89^{\circ} 15' E.$ 12.88 chains, to the mountain. The total length of said road being 160.00 chains.

Description of a County Road four rods wide leading from Main Street in Lyons at Shaw's store, Eastward to the Mountain.

3. Beginning at a certain monument of sandstone, situated in the center of Main Street in Lyons District 21.69 chains South and 10.911 chains West from the North East corner of Section 17, Township Six North of Range One West Salt Lake Meridian - known and designated as "Weber County Survey Monument No 6" - from which the bearings to DenLomond Peak are $N. 3^{\circ} 06' E.$ and to Observatory Peak $S. 48^{\circ} 46' E.$ running thence $S. 89^{\circ} 48' E.$ 99.20 chains to Monument No 88 - situated in the center of a street 4 rods in width intersecting the above described road and bearing

County Road Book,

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3rd
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book
 on page 356 &c.) the following described road was declared to be a County Road, to-wit:

1. Beginning at a monument of sandstone in the center of what is known as Main Street Ogden 347 ft. N. $89^{\circ}35'$ W. from the center of the dome on the Weber County Court House, and N $0^{\circ}25'$ E. 116.2 feet from the center of Fourth St. and running thence N. $25'$ E. 80.76 chains, to what is known and designated as Weber County Survey Monument No. 2, situated in the center of a road leading Eastward - continuing thence N. $25'$ E. 19.85 chains to the Quarter section line east and west through Section 20, Township 6, North Range 1 West, Salt Lake Meridian and to County Survey Monument No. 4, thence N. $15'$ E. 16.01 chains to Monument No. 3 situated in the center of streets leading east and west near the Mound Fort School House, thence N. $15'$ E. 41.21 chains to Monument No. 5 situated in the center of a street leading Eastward, thence continuing N. $15'$ E. 41.26 chains to Monument No. 6, situated in center of streets leading eastward and westward through Lynx District, thence continuing N. $15'$ E. 41.01 chains to Monument No. 7 situated in the center of a four rod street on the North boundary of Ogden City Corporation, leading eastward being 20.72 chains S. $15'$ W. and 10.56 chains West from the southeast corner of the Northeast Quarter of Section 8 Township 6 North of Range 1 West Salt Lake Meridian - the bearing from said Monument 7 to Observatory Peak being S. $45^{\circ}21'$ E. The total length of said road being 240.10 chains.