

Record of the County Court of Weber County, Utah Territory.

1881.

March 3.

South eastward to Lewis' Hoop's Factory. The bearings from said monument to the dome on the United States Observatory at Ogden being $S. 12^{\circ} 37' N.$ and to the spire on the Heber County Court House $S. 25^{\circ} 31' N.$ From thence the said road continues $S. 89^{\circ} 48' E.$ 30.00 chains to the mountain. Said road being 129.20 chains in length.

Description of a County Road four rods wide leading from Main Street in Lyman District Eastward on the North line of the Ogden City Corporation to the Mountains.

4. Beginning at a certain monument of sandstone situated in the center of Main Street in Lyman District, and on the North boundary of the Corporation of Ogden City 20.72 chains $S. 0^{\circ} 15' N.$ and 10.50 chains West from the South East corner of the North East Quarter of Section Eight Township Six North of Range One West Salt Lake Meridian. The bearing from said monument known as County Survey Monument No. 7 being to Observatory Peak $S. 45^{\circ} 31' E.$ running from thence $S. 89^{\circ} 42' E.$ 69.30 chains to Monument No. 92 at the intersection of a road leading Northward to North Ogden District. Thence $S. 89^{\circ} 42' E.$ 5.36 $\frac{3}{4}$ Monument No. 93 at the intersection of a road leading Southeastward to Ogden Canyon thence continuing $S. 89^{\circ} 42' E.$ 71.15 chains, to the mountain top. Said road being 145.81 chains in length.

Description of a County Road four rods wide leading from a point near Lewis' Hoop's Factory in Ogden Northward to the North boundary of the Ogden City Corporation.

5. Beginning in the center of the road leading from Ogden City to Ogden Valley at a point 22.65 chains East from the South West corner of the North West Quarter of Section Twenty Two, Township Six North of Range One West Salt Lake Meridian. The bearings from said point to the North East corner of said Hoop's Factory being $N. 67^{\circ} 49' N.$ Running thence $N. 29^{\circ} 32' E.$ 15.17 chains, thence $N. 19^{\circ} 35' N.$ 13.25 chains, thence $N. 2^{\circ} 20' E.$ 31.22 chains to Monument No. 89. thence $N. 23^{\circ} 04' N.$ 45.10 chains, to Monument No. 88. thence $N. 31^{\circ} N.$ 47.71 chains, to Monument No. 93 and intersecting the road on the Northern boundary of the Ogden City Corporation. Said road being 152.45 chains in length.

Description of a County Road eight rods wide leading Southward from Fourth Street in Ogden City.

6. Beginning at a sandstone monument known and designated as "Heber County Survey Monument No. 1," situated in the center of Main Street in Ogden City, distant 347 feet $N. 89^{\circ} 25' N.$ from the center of the dome on the Heber County Court House, and 116 $\frac{2}{3}$ feet $N. 0^{\circ} 25' E.$ from the center of Fourth Street in said City, and running from thence $S. 0^{\circ} 25' N.$ 48.00

Record of the County Court of Weber County, Utah Territory.

1895.

March 3.

chains to "County Survey Monument No. 47," situated on the point of the intersection of the centers of Eighth and Main Streets in Ogden City. Continuing thence $S. 0^{\circ} 25' N.$ 76.74 chains to "Monument No. 48" South end of the Weber County Base situated 12.16 chains West and 14.89 chains North from the South East corner of the North East Quarter of Section Five - Township 5 North of Range One West - Salt Lake Meridian. The dimensions of said monument are $8 \times 8 \times 18'$ and the bearing to Observatory Peak being $N. 89^{\circ} 52' E.$ The bearing to Berlonmond Peak being $N. 2^{\circ} 08' E.$ and the bearing to the spire on the Weber County Court House $N. 2^{\circ} 49' E.$ The total length of the above road is 124.74 chains.

Description of a County Road six rods wide known as South Street in Ogden City.

7. Beginning at a point in the center of Main Street 116 $\frac{1}{2}$ feet $S. 0^{\circ} 25' N.$ from what is known and designated as "Weber County Survey Monument No. 1," and 365 $\frac{1}{2}$ ft. $S. 71^{\circ} 53' N.$ from the center of the dome on the Weber County Court House and running from thence $N. 89^{\circ} 42' N.$ in the center of South Street 34.80 chains, to the center of Wall Street - thence $N. 89^{\circ} 28' N.$ 30.40 chains, to a point in the center of said street 99 feet $N. 17^{\circ} 02' E.$ from the center of the Main line of the Utah Central Railway track. thence continuing in the center of said street $N. 72^{\circ} 58' N.$ 13.61 chains, parallel to and distant 99 feet from the center of said Railway track, and to Monument No. 61 situated at the intersection of a road leading to West Weber District, being 11.37 chains $N. 72^{\circ} 58' N.$ from the West end of the wagon bridge across Weber River in Ogden. From this point the road continues four rods in width: $N. 72^{\circ} 58' N.$ 5.47 chains, thence South $80^{\circ} 00'$ West 5.97 chains, thence $N. 72^{\circ} 58' N.$ 9.25 chains parallel to and 85 $\frac{1}{2}$ feet South from the center of the Utah Central Railway track, thence due West 11.66 chains, thence $S. 66^{\circ} 49' N.$ 10.43 chains - thence $S. 50^{\circ} N.$ 9.78 chains, thence $S. 42^{\circ} 40' N.$ 22.59 chains - parallel to and distant 85 $\frac{1}{2}$ feet Eastward from the center of the above mentioned railway track - and to the North line of Section Thirty One (31) Township 6 North of Range One West - Salt Lake Meridian. thence West 3.37 chains, to "Monument No. 62" situated 3.00 chains East from the North West corner of the above mentioned Section 31. The bearings from said Monument are: To "Observatory Peak" $S. 78^{\circ} 38' E.$ To "Berlonmond Peak" $N. 12^{\circ} 49' \frac{1}{2}' E.$ Said road from its beginning to the above point being 157.35 chains in length. Also Beginning at the above described point of beginning, in the center of Main Street running thence $S. 89^{\circ} 35' E.$ to the East line of Section 28 Township Six North of Range One West - Salt Lake Meridian.

Description of a County Road four rods wide leading from Ogden City to Ogden Valley.

8. Beginning in the center of Main Street in Ogden City at a point 1.12 chains $N. 63^{\circ} 05' N.$ from the

Weber County, Utah.

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3rd
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book
 on page 358-9 &c.) the following described road was declared to be a County Road, to-wit:

6. Southward from Fourth Street in Ogden City: —

Beginning at a sandstone monument known and designated as Weber County Survey Monument No. 1 situated in the center of Main Street in Ogden City, distant 347 feet N. $89^{\circ}35'$ E. from the center of the dome on the Weber County Court House — and 116.2 feet N. $25'$ E. from the center of Fourth Street in said city — and running from thence S. $25'$ E. 48 chains to the County Monument No. 47 situated on the point of the intersection of the centers of 8th and Main Streets in Ogden City. Continuing thence S. $25'$ E. 76.74 chains to Monument No. 48 south end of the Weber County base — situated 12.16 chains west and 14.89 chains north from the southeast corner of the northwest quarter of Section 5 Township 5 North of Range \pm N. Salt Lake Meridian — The dimensions of said monument are $8" \times 8" \times 48"$ and the bearing to Observatory Peak

being N. $89^{\circ}52'$ E. The bearing to Ben Lomond Peak ^{and the bearing to spire on Weber Co. Court House is N. $72^{\circ}19'$ E.} being N. $2^{\circ}08'$ E. The total length of the above road is 124.74 chains.