

## Record of the County Court of Weber County, Utah Territory.

1895.

March 3.

chains to "County Survey Monument No. 47," situated on the point of the intersection of the centers of Eighth and Main Streets in Ogden City. Continuing thence  $S. 0^{\circ} 25' N.$  76.74 chains to "Monument No. 48" South end of the Weber County Base situated 12.16 chains West and 14.89 chains North from the South East corner of the North East Quarter of Section Five - Township 5 North of Range One West - Salt Lake Meridian. The dimensions of said monument are  $8 \times 8 \times 18$  and the bearing to Observatory Peak being  $N. 89^{\circ} 52' E.$  The bearing to Berlonmond Peak being  $N. 2^{\circ} 08' E.$  and the bearing to the spire on the Weber County Court House  $N. 2^{\circ} 49' E.$  The total length of the above road is 124.74 chains.

Description of a County Road six rods wide known as South Street in Ogden City.

7. Beginning at a point in the center of Main Street 116  $\frac{3}{4}$  feet  $S. 0^{\circ} 25' N.$  from what is known and designated as "Weber County Survey Monument No. 1," and 365  $\frac{1}{4}$  ft.  $S. 71^{\circ} 53' N.$  from the center of the dome on the Weber County Court House and running from thence  $N. 89^{\circ} 42' N.$  in the center of South Street 34.80 chains, to the center of Wall Street - thence  $N. 89^{\circ} 28' N.$  30.40 chains, to a point in the center of said street 99 feet  $N. 17^{\circ} 02' E.$  from the center of the Main line of the Utah Central Railway track. thence continuing in the center of said street  $N. 72^{\circ} 58' N.$  13.61 chains, parallel to and distant 99 feet from the center of said Railway track, and to Monument No. 61 situated at the intersection of a road leading to West Weber District, being 11.37 chains  $N. 72^{\circ} 58' N.$  from the West end of the wagon bridge across Weber River in Ogden. From this point the road continues four rods in width:  $N. 72^{\circ} 58' N.$  5.47 chains, thence South  $80^{\circ} 00'$  West 5.97 chains, thence  $N. 72^{\circ} 58' N.$  9.25 chains parallel to and 85  $\frac{1}{2}$  feet South from the center of the Utah Central Railway track, thence due West 11.66 chains, thence  $S. 66^{\circ} 49' N.$  10.43 chains - thence  $S. 50^{\circ} N.$  9.78 chains, thence  $S. 42^{\circ} 40' N.$  22.59 chains - parallel to and distant 85  $\frac{1}{2}$  feet Eastward from the center of the above mentioned railway track - and to the North line of Section Thirty One (31) Township 6 North of Range One West - Salt Lake Meridian. thence West 3.34 chains, to "Monument No. 62" situated 3.00 chains East from the North West corner of the above mentioned Section 31. The bearings from said Monument are: To "Observatory Peak"  $S. 78^{\circ} 38' E.$  To "Berlonmond Peak"  $N. 12^{\circ} 49' \frac{1}{2}' E.$  Said road from its beginning to the above point being 157.35 chains in length. Also Beginning at the above described point of beginning, in the center of Main Street running thence  $S. 89^{\circ} 35' E.$  to the East line of Section 28 Township Six North of Range One West - Salt Lake Meridian.

Description of a County Road four rods wide leading from Ogden City to Ogden Valley.

8. Beginning in the center of Main Street in Ogden City at a point 1.12 chains  $N. 63^{\circ} 05' N.$  from the

## County Road Book,

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3<sup>rd</sup>  
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book  
 on page \_\_\_\_\_ &c.) the following described road was declared to be a County Road, to-wit:

7. Fourth Street Ogden City; —  
 Beginning at a point in the center of Main Street 116.2 feet South 25' W. from what is known and designated as Weber County Survey Monument No. 1 and 365.6 ft S. 71° 53' W. from the center of the dome on the Weber County Court House — and running from thence N. 89° 42' W. in the center of Fourth Street 34.80 chains, to the center of Hall Street, thence N. 89° 28' W. 30.40 chains to a point in the center of said street 99 ft N. 17° 02' E. from the center of the main line of U. C. R. R. track thence continuing in the center of said street N. 72° 58' W. 13.61 chains parallel to and distant 99 ft. from the center of said R. R. track, and to Monument No. 61 situated at the intersection of a road leading to West Weber District, being 4.37 chains N. 72° 58' W. from the west end of the wagon bridge across the Weber river in Ogden. From this point the road continues four rods in width N. 72° 58' W. 5.47 chains, thence south 80° W. 5.97 chains, thence N. 72° 58' W. 9.25 chains parallel to and 85½ ft. south from the center of U. C. R. R. track, thence due west 11.66 chains, thence S. 66° 49' W. 10.43 chains — thence S. 50° W. 9.78 chains, thence S. 42° 40' W. 22.59 chains parallel to and distant 85½ ft. eastward from the center of the above mentioned R. R. track — and to the north line of section 31, Township 6, North of Range 1 N. Salt Lake Meridian, thence west 3.39 chains to Monument 62 situated 3 chains E. from the northwest corner of the above mentioned Section 31. The bearings from said monument are: To Observatory Peak S. 78° 38' E., To Ben Lounnon Peak, N. 12° 49½' E. Said road from its beginning to the above point being 159.35 chains in length. Also beginning at the above described point of beginning in the center of Main Street and running thence S. 89° 35' E. to the east line of Section 28 Township 6 north of Range 1 West — Salt Lake Meridian