

## Record of the County Court of Weber County, Utah Territory.

1885

March 3.

S.  $56^{\circ} 53\frac{1}{2}'$  E. running thence S.  $89^{\circ} 45' E$ . 85.11 chains - following the center of said street thence S.  $50^{\circ} 45' E$ . 10.06 chains intersecting the road from Ogden City to Ogden Valley at Monument No. 90 situated 9.11 chains North and 2.62 chains East from the South West corner of the North West Quarter of Section Twenty Two Township Six North of Range Two West Salt Lake Meridian. The bearings from said Monument being to Benlomonde Peak N.  $5^{\circ} 12' N$  to Observatory Peak S.  $49^{\circ} 39' E$ . and to the North East corner of the main building of the Weber Factory S.  $39^{\circ} 22' N$  2.06 chains. Said road being 95.20 chains in length from its beginning to this point.

Description of a County Road four rods wide leading from Monument No. 3 described above, Westward, through Marriottville.

10. Beginning at the center of Main Street at what is known and designated as Monument No. 3 near the Monnds Fort Schoolhouse - and running thence N.  $89^{\circ} 45' N$  29.00 chains in the center of said road - thence S.  $77^{\circ} 09' N$  4.32 chains - thence N.  $87^{\circ} 27' N$  8.64 chains, thence N.  $89^{\circ} 38\frac{1}{2}' N$  122.31 chains to Monument No. 78, situated in the center of the street near the Marriotts District Schoolhouse, thence continuing N.  $87^{\circ} 38\frac{1}{2}' N$  79.00 chains to Weber River. Total length 243.27 chains.

Description of a County Road four rods wide leading from Marriotts District Schoolhouse, Northward to Slaterville District.

11. Beginning in the center of the street near the above mentioned Schoolhouse at a certain Monument known and designated as County Survey Monument No. 78 with bearings as follows: to Benlomonde Peak N.  $16^{\circ} 40\frac{1}{2}' E$ . to Observatory Peak S.  $65^{\circ} 43' E$  running from thence N.  $60^{\circ} 58' N$  39.07 chains to Monument No. 79, situated in the center of said street N.  $30^{\circ} 12' N$  from the South East corner of Section Thirteen Township Six North of Range Two West Salt Lake Meridian - continuing thence N.  $0^{\circ} 58' N$  12.30 chains to the South bank of Mill Creek, thence N.  $55^{\circ} 04\frac{1}{2}' E$ . 3.12 chains - thence N.  $0^{\circ} 31\frac{1}{2}' N$  29.51 chains, to Monument No. 80 situated in the center of the road leading Westward through Lyme District - being 22.63 chains North and 9.51 chains West from the South East corner of the North East Quarter of Section Thirteen Township Six North of Range Two West Salt Lake Meridian. The total length of said road being 84.00 chains from its beginning to this point.

Description of a County Road four rods wide leading from Shaw's in Lyme Westward to Slaterville.

12. Beginning at a certain monument of sandstone, situated in the center of Main Street

## Record of the County Court of Weber County, Utah Territory.

1883.

March 3.

in Lyme District 21.69 chains South, and 10.94 chains West from the North East corner of Section Seventeen, Township Six North, of Range One West, Salt Lake Meridian, known and designated as Weber County Survey Monument Number Six from which the bearings to Benlonsard Peak are  $N. 3^{\circ} 06' E.$  and to Observatory Peak  $S. 48^{\circ} 46\frac{1}{2}' E.$  running from thence  $N. 89^{\circ} 48' N. \frac{5}{10}$  of one chain to what is known as Weber County Survey Monument Number 22 at the intersection of a road leading Northwestward to Harrisville, thence  $N. 89^{\circ} 48' N. 162.91$  chains, to Monument Number 80, situated in the center of a road leading Southward to Marnitts Schoolhouse and being 22.63 chains North and 9.51 chains West from the South East corner of the North East Quarter of Section Thirteen, Township Six North, of Range Two West, Salt Lake Meridian. The total length of said road to the above point being 163.44 chains.

Description of a County Road six rods wide leading from Shaw's store in Lyme North westward through Harrisville to the Hot Springs.

13. Beginning at a certain monument of sandstone, situated  $\frac{5}{10}$  of one chain  $N. 89^{\circ} 48' N.$  from the center of Main Street near Shaw's store in Lyme District 21.69 chains South and 11.47 chains West from the North East corner of Section Seventeen, Township Six North, of Range One West, Salt Lake Meridian, known and designated as Weber County Survey Monument Number Twenty Two (22) running from thence  $N. 25^{\circ} 30' N. 68.62$  chains in the center of said street, thence  $N. 39^{\circ} 45' N. 8.23$  chains to Weber County Survey Monument No. 23 at the intersection of the center of a road 4 rods in width leading  $N. 60^{\circ} E. 11.08$  chains, to the center of Main Street, thence  $N. 68^{\circ} N. 1365$  chains, thence  $N. 50^{\circ} 25' N. 28.26$  chains, thence  $N. 30^{\circ} 35' N. 14.28$  chains to Weber County Survey Monument No. 24 situated  $N. 78^{\circ} 18' N.$  from the South East corner of Section Six Township Six North of Range One West, Salt Lake Meridian, running from thence due North 17.93 chains thence  $N. 66^{\circ} 30' N. 38.65$  chains to Monument No. 25 situated at the intersection of the center of a street leading to Pleasant View District. Said monument being  $S. 35^{\circ} 47' N. 6.16$  chains from the North East corner of the South West Quarter of Section Six Township Six North of Range One West, Salt Lake Meridian, continuing thence  $N. 66^{\circ} 30' N. 23.02$  chains to Monument No. 26, thence due West 27.86 chains to Monument No. 27, situated at the intersection of the center of a street four rods in width leading Southward to Slatonville District and to Monument No. 80, thence  $S. 87^{\circ} 52' N. 17.90$

# Weber County, Utah.

95

At a session of the County Court of Weber County, in the Territory of Utah, held on the <sup>3<sup>rd</sup></sup>  
day of March A. D. 1866 (the minutes of the proceedings of which are recorded in County Book  
C on page 162-3 &c.) the following described road was declared to be a County Road, to-wit:

From Shaw's in Lynae, westward to Slaterville.

Beginning at a certain Monument of sandstone, situated in the center of Main Street in Lynae District 21.69 chains south and 10.94 chains east from the Northeast corner of Section 17, Township 6, North of Range One West Salt Lake Meridian, known and designated as Weber County Survey Monument No. 6, from which the bearings to Ben Lomas Peak are  $N. 3^{\circ} 06' E.$  and to Observatory Peak  $S. 48^{\circ} 46\frac{1}{2}' E.$  running from thence  $N. 89^{\circ} 48' W. 53$  of a chain to what is known as Weber County Survey Monument No. 22 at the intersection of a road leading northward to Harrisville, thence  $N. 89^{\circ} 48' W. 162.91$  chains to Monument No. 60, situated in the center of a road leading southward to Marriotts School house and being 22.63 chains North and 9.51 chains West from the southeast corner of Northeast Quarter of Section 13, Township 6 North of Range Two West, Salt Lake Meridian. The total length of said road to the above point 163.44 chains.