

Record of the County Court of Weber County, Utah Territory.

1885

March 3.

Description of a County Road four rods wide leading from North Ogden to intersect the road from North Ogden to the Hot Springs.

16. Beginning at a certain monument of sandstone situated in the center of what is known as Main Street in North Ogden, 100 chain East and $\frac{50}{100}$ of one chain South from the South East corner of Lot 48, Plat "B," North Ogden Survey, known and designated as Weber County Survey Monument No. 14, from which the bearing to Benlmond Peak is $N. 5^{\circ} 11' E.$ and to Observatory Peak, $S. 32^{\circ} 49' E.$ running from thence $N. 87^{\circ} 41\frac{1}{2}' N. 114.34$ chains, to Monument No. 91, at the intersection of the center of a road four rods in width leading Southward to Harrisville, bearings from said monument to Benlmond Peak $N. 23^{\circ} 54' E.$ to Observatory Peak $S. 40^{\circ} 11\frac{1}{2}' E.$ thence continuing $N. 87^{\circ} 41\frac{1}{2}' N. 28.10$ chains, to Monument No. 95, thence $N. 0^{\circ} 33\frac{1}{2}' E. 96.92$ chains to Monument No. 19 at the intersection of the center of the Main Street 8 rods in width leading through Pleasant View to the Hot Springs - the bearings from said monument to Benlmond Peak are $N. 36^{\circ} 56' E.$ and to Observatory Peak $S. 37^{\circ} 20' E.$ Said road is 239.66 chains in length.

Description of a County Road four rods wide leading from Harrisville Northward & intersecting a road leading Westward from North Ogden.

17. Beginning at a certain monument of sandstone situated in the center of the road six rods in width leading Northwestward through Harrisville District to the Hot Springs, at a point $S. 35^{\circ} 47' N. 6.16$ chains, from the North East corner of the South West Quarter of Section Six, Township Six, North of Range One West Salt Lake Meridian, said monument being known and designated as Weber County Survey Monument No. 25 - bearings to Observatory Peak being $S. 46^{\circ} 15' E.$ running from thence $N. 0^{\circ} 14' N. 110.78$ chains, to Monument No. 94 at the intersection of the center of a street four rods in width leading Eastward to North Ogden. Said road is 110.78 chains in length.

Description of a County Road four rods wide leading from Main Street in North Ogden Eastward to North Ogden Canyon.

18. Beginning at a certain monument of sandstone situated in the center of Main Street in North Ogden, 100 chain West and $\frac{50}{100}$ of one chain South from the South West corner of Block Eight Plat "A" North Ogden Survey, ^{in Weber County} known and designated as Weber County Survey Monument No. 13, from which the bearing to Benlmond Peak is $N. 5^{\circ} 24\frac{1}{2}' E.$ and to the South gable of the North Ogden meeting house $N. 87^{\circ} 58\frac{1}{2}' E.$ and running from thence due East, 57.36 chains to Monument

Weber County, Utah.

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3rd day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book C on page 366 &c.) the following described road was declared to be a County Road, to-wit:

16. From North Ogden to intersect road from North Ogden to Hot Springs. Beginning at a certain monument of sandstone situated in the center of what is known as Main Street in North Ogden, one chain east and .50 of a chain south from the southeast corner of Lot 48, Plat B, North Ogden Survey, known and designated as Weber County Survey Monument No. 14, from which the bearing to Ben Lomond Peak is N. 5° 14' E. and to Observatory Peak is S. 32° 49' E. running from thence N. 89° 41½' St. 114.44 chains, to Monument No. 94, at the intersection of the center of the road four rods in width leading southward to Harveysville, bearing from said Monument to Ben Lomond Peak N. 23° 54' E. and to Observatory Peak S. 40° 11½' E. thence continuing N. 89° 41½' St. 38.40 chains to Monument No. 95, thence N. 33½' E. 96.92 chains to Monument No. 19 at the intersection of the center of the Main Street Road in width leading through Pleasant View to Hot Springs, the bearing from said Monument to Ben Lomond Peak N. 36° 56' E. and to Observatory Peak S. 34° 20' E. Said road is 239.66 chains in length.