

Record of the County Court of Weber County, Utah Territory.

1885

March 3.

Description of a County Road four rods wide leading from North Ogden to intersect the road from North Ogden to the Hot Springs.

16. Beginning at a certain monument of sandstone situated in the center of what is known as Main Street in North Ogden, 100 chain East and $\frac{50}{100}$ of one chain South from the South East corner of Lot 48, Plat "B," North Ogden Survey, known and designated as Weber County Survey Monument No. 14, from which the bearing to Benlmond Peak is $N. 5^{\circ} 11' E.$ and to Observatory Peak $S. 32^{\circ} 49' E.$ running from thence $N. 87^{\circ} 41\frac{1}{2}' N. 114.34$ chains, to Monument No. 94, at the intersection of the center of a road four rods in width leading Southward to Harrisville, bearings from said monument to Benlmond Peak $N. 23^{\circ} 54' E.$ to Observatory Peak $S. 40^{\circ} 11\frac{1}{2}' E.$ thence continuing $N. 87^{\circ} 41\frac{1}{2}' N. 28.10$ chains, to Monument No. 95, thence $N. 0^{\circ} 33\frac{1}{2}' E. 96.92$ chains to Monument No. 19 at the intersection of the center of the Main Street roads in width leading through Pleasant View to the Hot Springs - the bearings from said monument to Benlmond Peak are $N. 36^{\circ} 56' E.$ and to Observatory Peak $S. 37^{\circ} 20' E.$ Said road is 239.66 chains in length.

Description of a County Road four rods wide leading from Harrisville Northward & intersecting a road leading Westward from North Ogden.

17. Beginning at a certain monument of sandstone situated in the center of the road six rods in width leading Northwestward through Harrisville District to the Hot Springs, at a point $S. 35^{\circ} 47' N. 6.16$ chains, from the North East corner of the South West Quarter of Section Six, Township Six North of Range One West Salt Lake Meridian, said monument being known and designated as Weber County Survey Monument No. 25 - bearings to Observatory Peak being $S. 46^{\circ} 15' E.$ running from thence $N. 0^{\circ} 14' N. 110.78$ chains, to Monument No. 94 at the intersection of the center of a street four rods in width leading Eastward to North Ogden. Said road is 110.78 chains in length.

Description of a County Road four rods wide leading from Main Street in North Ogden Eastward to North Ogden Canyon.

18. Beginning at a certain monument of sandstone situated in the center of Main Street in North Ogden 100 chain West and $\frac{50}{100}$ of one chain South from the South West corner of Block Eight Plat "A" North Ogden Survey, ^{in Weber County} known and designated as Weber County Survey Monument No. 13, from which the bearing to Benlmond Peak is $N. 5^{\circ} 24\frac{1}{2}' E.$ and to the South gable of the North Ogden meeting house $N. 87^{\circ} 58\frac{1}{2}' E.$ and running from thence due East 57.36 chains to Monument

County Road Book,

At a session of the County Court of Weber County, in the Territory of Utah, held on the 13th
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book
 C on page 366 &c.) the following described road was declared to be a County Road, to-wit:

17. From Harrisville northward intersecting a road leading westward from North Ogden
 Beginning at a certain monument of sandstone situated in
 the center of a road six rods in width leading northeastward through
 Harrisville District to the Hot Springs, at a point S. 35° 47' W. 6.16 chains,
 from the Northeast Corner of the Southwest Quarter of Section
 6, Township 6 North of Range One West, Salt Lake Meridian,
 said monument being known and designated as Weber
 County Survey Monument No. 25, bearings to Observatory
 Peak being S. 46° 15' E. running from thence N 14° W.
 110.78 chains, to Monument No. 94, at the intersection of
 the center of a street four rods in width leading east-
 ward to North Ogden. Said road is 110.78 chains in
 length.