

Record of the County Court of Weber County, Utah Territory.

1885

March 3.

Description of a County Road four rods wide leading from North Ogden to intersect the road from North Ogden to the Hot Springs.

16. Beginning at a certain monument of sandstone situated in the center of what is known as Main Street in North Ogden, 100 chain East and $\frac{50}{100}$ of one chain South from the South East corner of Lot 48, Plat "B," North Ogden Survey, known and designated as Weber County Survey Monument No. 14, from which the bearing to Benlmond Peak is $N. 5^{\circ} 11' E.$ and to Observatory Peak, $S. 32^{\circ} 49' E.$ running from thence $N. 87^{\circ} 41\frac{1}{2}' N. 114.34$ chains, to Monument No. 91, at the intersection of the center of a road four rods in width leading Southward to Harrisville, bearings from said monument to Benlmond Peak $N. 23^{\circ} 54' E.$ to Observatory Peak $S. 40^{\circ} 11\frac{1}{2}' E.$ thence continuing $N. 87^{\circ} 41\frac{1}{2}' N. 28.10$ chains, to Monument No. 95, thence $N. 0^{\circ} 33\frac{1}{2}' E. 96.92$ chains to Monument No. 19 at the intersection of the center of the Main Street 8 rods in width leading through Pleasant View to the Hot Springs - the bearings from said monument to Benlmond Peak are $N. 36^{\circ} 56' E.$ and to Observatory Peak $S. 37^{\circ} 20' E.$ Said road is 239.66 chains in length.

Description of a County Road four rods wide leading from Harrisville Northward & intersecting a road leading Westward from North Ogden.

17. Beginning at a certain monument of sandstone situated in the center of the road six rods in width leading Northwestward through Harrisville District to the Hot Springs, at a point $S. 35^{\circ} 47' N. 6.16$ chains, from the North East corner of the South West Quarter of Section Six, Township Six, North of Range One West Salt Lake Meridian, said monument being known and designated as Weber County Survey Monument No. 25 - bearings to Observatory Peak being $S. 46^{\circ} 15' E.$ running from thence $N. 0^{\circ} 14' N. 110.78$ chains, to Monument No. 94 at the intersection of the center of a street four rods in width leading Eastward to North Ogden. Said road is 110.78 chains in length.

Description of a County Road four rods wide leading from Main Street in North Ogden Eastward to North Ogden Canyon.

18. Beginning at a certain monument of sandstone situated in the center of Main Street in North Ogden, 100 chain West and $\frac{50}{100}$ of one chain South from the South West corner of Block Eight Plat "A" North Ogden Survey, ^{in Weber County} known and designated as Weber County Survey Monument No. 13, from which the bearing to Benlmond Peak is $N. 5^{\circ} 24\frac{1}{2}' E.$ and to the South gable of the North Ogden meeting house $N. 87^{\circ} 58\frac{1}{2}' E.$ and running from thence due East, 57.36 chains to Monument

Record of the County Court of Weber County, Utah Territory.

1888.

March 3.

No. 42, situated in the intersection of the center of a road four rods in width leading South eastward to David Garner's residence, continuing from thence due East 10.98 chains, thence N. $5^{\circ} 48' E$. 41.07 chains thence due East 19.81 chains, thence N. $0^{\circ} 15' N$. 19.95 chains to Monument No. 44, situated at the intersection of the center of a road four rods in width leading West $\frac{1}{2}$ of one leading North to the mountains, said point being also the South East corner of the North East Quarter of the South East Quarter of Section Twenty Eight (28) Township Seven North of Range One West, Salt Lake Meridian, thence due East 57.78 chains to Monument No. 45, situated at the intersection of the center of a street four rods in width leading Southwestward to the North line of Ogden City Corporation, thence N. $75^{\circ} E$. 8.31 chains thence due North 9.98 chains to Monument No. 43, at the Western mouth of "Ogden Hole Canyon," the bearing from said monument to the North Ogden meeting house being $S 71^{\circ} 25' N$. The total length of said road from its beginning to this point is 188.24 chains.

Description of a County Road four rods wide leading from a point near the Western mouth of Ogden Hole Canyon, Southward to the Northern boundary of the Ogden City Corporation.

- 19 Beginning at a certain monument of sandstone situated 19.95 chains N. $0^{\circ} 15' N$ and 57.78 chains due East from the South West corner of Section Twenty Seven (27) Township Seven North of Range One West, Salt Lake Meridian, known and designated as Weber County Survey Monument No. 45, at the center of a road ^{four rods in width} leading to North Ogden, running from thence S. $25^{\circ} N$. 72.33 chains, thence S. $12^{\circ} 20' N$. 13.88 chains thence S. $37^{\circ} 27' N$. 24.77 chains to a point 8.55 chains due East from the North West corner of Section Three (3) Township Six North of Range One West of Salt Lake Meridian, thence S. $13^{\circ} 10' N$. 22.93 chains, to the intersection of the center of a street leading to North Ogden, thence S. $66^{\circ} 51' N$. 2.82 chains, thence S. $38^{\circ} N$. 7.24 chains, thence S. $7^{\circ} 22' N$. 20.91 chains, thence S. $1^{\circ} 50' N$. 17.37 chains, thence S. $14^{\circ} 23' N$. 53.07 chains thence due South 21.15 chains to Monument No. 92, situated at the center of a street four rods in width running Westward to Main Street on the Northern boundary of Ogden City ^{Corporation}. The above described road is 258.47 chains in length from its beginning to this point.

Description of a County Road four rods wide running Northward from North Ogden, on the East line of Section Twenty Eight (28) Township Seven North of Range One West, Salt Lake Meridian.

- 20 Beginning at a certain monument of sandstone situated on the Southeast corner of the North

Weber County, Utah.

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3rd
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book
 C on page 366-7 &c.) the following described road was declared to be a County Road, to-wit:

18. From Main Street in North Ogden eastward to North Ogden Canyon.
 Beginning at a certain Monument of sandstone situated in the center of Main Street in North Ogden, 1 chain West and .50 chain South from the southwest corner of Block 8, Plat A, North Ogden Survey in Weber County, known and designated as Weber County Survey Monument No. 13 from which the bearing to Ben Lomond Peak is $N. 5^{\circ} 24\frac{1}{2}' E.$ and to the south gable of the North Ogden meeting-house $N. 87^{\circ} 58\frac{1}{2}' E.$ and running from thence due east 57.36 chains to Monument No. 42, situated in the intersection of the center of a road four rods in width leading southeastward to David Garner's residence, continuing from thence due east 10.98 chains, thence $N. 5^{\circ} 48' E.$ 4.07 chains thence due east 19.81 chains, thence $N. 15' S.$ 19.95 chains to Monument No. 44, situated at the intersection of the center of a road four rods in width leading eastward of one leading North to the Mountains, said point being also the southeast corner of the Northeast Quarter of the southeast Quarter of Section 28, Township 7, North of Range One west, Salt Lake Meridian, thence due east 57.78 chains to Monument No. 45 situated at the center of a street four rods in width leading southeastward to the North Line of Ogden City Corporation, thence $N. 25^{\circ} E.$ 8.31 chains, thence due north 9.98 chains to Monument No. 43, at the western mouth of Ogden Hall Canyon, the bearing from said Monument to the North Ogden meeting house being $S. 71^{\circ} 25' S.$ The total length of said road from its beginning to this point being 188.24 chains.

Apr. 19th 1897 Business, to continue during the absence of this board.

Commissioner Armstrong reported that William M. Bostaph had made verbal application to him for the office of County Surveyor. Commissioner Seaman reported that he had investigated the matter of granting the petition of Henry Benson, et al., for the reopening of a road running east and west commencing at road East of the South-west corner of Lot 1, Block 14, Plat A of North Ogden Survey, alleged to have been closed by one James Shufes. Commissioner Seaman stated that after a very careful examination of the records, records, and the premises in question, he would recommend that the prayer of the petition be granted, that the road be reopened to the travelling public, that James Shufes be required to forthwith remove any fences or obstructions which may be upon said road, and that the Road Supervisor of North Ogden be directed to see that these orders be carried into effect. This recommendation was unanimously adopted. A communication of which the following is a copy was read, and a resolution of Commissioner Seaman thereon was taken upon a division, to wit:-

April 19th, 1897

To the Hon. Board of County Commissioners of Weber County, Utah.

Dear Sirs:-

Your underigned, your petitioners, respect-

County Road Book,

At a session of the County Court of Weber County, in the Territory of Utah, held on the 19th
 day of April A. D. 1897 (the minutes of the proceedings of which are recorded in County Book
K on page 184 &c.) the following described road was declared to be a County Road, to-wit:

In North Ogden:—

The petition of Henry Barker et al,
 praying that a road running east and
 commencing about 21 rods East of the Southeast
 corner of Lot 1, Block 1st, Plat "A" of North Ogden
 Survey, alleging to have been closed by one, James
 Spruce. Upon recommendation of Commissioner
 Seaman, the petition was granted.