

Record of the County Court of Weber County, Utah Territory.

1885

March 3.

244.85 chains running from thence N. $18^{\circ} 20' E$. 111.03 chains, thence West 21.07 chains, thence due North 7.48 chains, thence West 9.48 chains, thence North 11.38 chains, thence West 2.47 chains, thence N. $0^{\circ} 27' E$. 9.59 chains, to Monument No. 37, situated $\frac{1}{100}$ of one chain South and $\frac{1}{100}$ of one chain West from the South West corner of Lot Ten, Plat "B" Plain City Survey bearings to Benlornond Peak being N. $53^{\circ} 27' E$ and to Observatory Peak $89^{\circ} 01\frac{1}{2}' E$ and to Egypt Peak $83^{\circ} 41\frac{1}{2}' E$ and in the center of a street leading Eastward to Harrisville. The total length of said road being 457.62 chains from its beginning to this point.

Description of a County Road four rods wide leading from a point near the residence of William Price in Harrisville, Westward through Slaterville to the Slaterville schoolhouse.

30. Beginning at a certain monument of sandstone situated in the center of a road leading Northward to Slaterville and Lyman District. The bearings from said monument being: to Benlornond Peak N. $17^{\circ} 42' E$ and to Egypt Peak N. $66^{\circ} 41' E$ and to Observatory Peak $82^{\circ} 21\frac{1}{2}' E$ and to the United States Observatory at Ogden $82^{\circ} 17' E$ and to the South East corner of Section Thirteen Township Six North of Range Six West Salt Lake Meridian $83^{\circ} 12' E$, said monument being known and designated as Weber County Survey Monument No. 79, running thence N. $89^{\circ} 57' N$. 80.38 chains to Monument No. 81, thence due North 18.06 chains, thence N. $78^{\circ} N$. 10.34 chains, thence due North 19.20 chains, thence N. $74^{\circ} 20' N$. 3.24 chains, thence N. $42^{\circ} N$. 5.21 chains thence N. $89^{\circ} 51' N$. 3.65 chains, to Monument No. 82, situated in the center of a street leading Westward, thence N. $1^{\circ} 30' E$. 22.62 chains, thence N. $65^{\circ} E$. 3.20 chains, thence N. $8^{\circ} 29' E$. 3.48 chains, to Monument No. 83, situated at the intersection of the center of a street leading Northward and Westward through Slaterville, and being near the Slaterville schoolhouse. The bearings from said monument being, to Benlornond Peak N. $28^{\circ} 10' E$, to Egypt Peak N. $79^{\circ} 13' E$, and to Observatory Peak $86^{\circ} 07\frac{1}{2}' E$. The total length of said road being 166.38 chains.

Description of a County Road four rods wide leading from a point near the residence of John Alfred, in Slaterville District, and running North and Westward to County Survey Monument No. 84, near the residence of Henry Bouns in Slaterville.

31. Beginning at a certain monument of sandstone situated in the center of the street leading Northwestward through Slaterville to Plain City, near the residence of John Alfred in Slaterville, known and designated as Weber County Survey Monument No. 85. The bearings from said monument being as follows: to Benlornond Peak

At a session of the County Court of Weber County, in the Territory of Utah, held on the ^{3rd} day of March A. D. 1886 (the minutes of the proceedings of which are recorded in County Book 372 &c.) the following described road was declared to be a County Road, to-wit:

From Marietta to Slaterville: -

Beginning at a certain monument of sandstone situated in the center of a road leading northward to Slaterville and Lyman Districts; the bearing from said monument being to Ben Leonard Peak N. $17^{\circ}42'$ E. and to Eyrice Peak N. $66^{\circ}44'$ E. and to Observatory Peak S. $62^{\circ}21\frac{1}{2}'$ E. and to the United States Observatory at Ogden S. $20^{\circ}17'$ E. and to the southeast corner of Section 13, Township 6 North of Range 2 West, Salt Lake Meridian, S. $30^{\circ}12'$ E. said monument being known and designated as Weber County Survey Monument No. 79, running thence N. $89^{\circ}57'$ W. 80.38 chains to Monument No. 81, thence due north 15.06 chains, thence N. 78° W. 10.34 chains, thence due north 19.20 chains, thence N. $74^{\circ}25'$ W. 3.24 chains thence N. 42° W. 5.21 chains, thence N. $89^{\circ}51'$ W. 3.65 chains, to Monument No. 82 situated in the center of a street leading westward, thence N. $1^{\circ}50'$ E. 27.62 chains, thence N. 65° E. 3.20 chains, thence N. $8^{\circ}29'$ E. 3.48 chains, to Monument No. 83, situated at the intersection ^{of the center} of a road leading northward and westward, through Slaterville, and being near the Slaterville school-house. The bearings from said monument being to Ben Leonard Peak N. $28^{\circ}15'$ E. to Eyrice Peak N. $49^{\circ}13'$ E. and to Observatory Peak S. $61^{\circ}7\frac{1}{2}'$ E. The total length of said road being 166.38 chains.