

Record of the County Court of Weber County, Utah Territory.

1885.

March 3.

chains, thence $S. 64^{\circ} 02' E.$ 2.68 chains, thence $S. 4^{\circ} 50' N.$ 10.81 chains, thence $S. 69^{\circ} 31' E.$ 8.83 chains, to the intersection of the center of a street leading Southward to the railway station at Uintah, thence continuing $S. 69^{\circ} 31' E.$ $\frac{83}{100}$ of one chain, thence $S. 83^{\circ} 23' E.$ 20.62 chains, thence $S. 89^{\circ} E.$ 11.38 chains, thence $S. 1^{\circ} N.$ 7.93 chains, to a point in the center of a road which leads $S. 1^{\circ} N.$ 7.43 chains, thence $S. 85^{\circ} 30' E.$ 26.88 chains, thence due South 29.26 chains, to the channel of the Weber River, which forms part of the Southern boundary line of Weber County, in Uintah District. The total length of the above road is 529.81 chains.

Description of a County Road two rods wide leading out of the main road which leads to Uintah, South to the Railway Station at Uintah.

- 38 Beginning at a point 21.73 chains West and 1.32 chains South from the North East corner of Section Twenty Seven Township Five North of Range One West, Salt Lake Meridian, from which point the bearing to the West gable of the school house at Uintah is $S. 75^{\circ} 20' E.$ - running from thence due South in the center of said road 13.87 chains, thence West 2.25 chains, thence South 2.30 chains, to a point on the South side of the Railway Station at Uintah. Said road being 17.42 chains in length.

Description of a County Road eight rods wide leading Southward from Ogden City, through Riverdale District and to the Southern boundary line of Weber County.

- 39 Beginning at a certain monument of sandstone situated in the center of Main Street in the Southern part of Ogden City 12.16 chains West and 11.89 chains North from the South East corner of the North East Quarter of Section No. Five, Township Five North, of Range One West, Salt Lake Meridian, being known and designated as Weber County Survey Monument No. 48, at the South end of the Weber County base. The dimensions of said monument are $8' \times 8' 11.8'$; - the bearings from said monument being as follows: to Observatory Peak $N. 89^{\circ} 52' E.$ to Benlornond Peak $N. 2^{\circ} 08' E.$, to the spire on the Weber County Court House $N. 2^{\circ} 49' E.$ and to the U. S. Observatory $N. 43^{\circ} 01' N.$ running from thence $S. 37^{\circ} 48' N.$ 45.16 chains, to Monument No. 52, situated at the intersection of a street four rods in width leading Southeastward to the Ogden City Hospital, thence continuing $S. 37^{\circ} 48' N.$ 42.10 chains, to the intersection of the center of a street four rods in width leading Westward near the

Record of the County Court of Weber County, Utah Territory.

1885

March 3.

residence of Rufus Allen, thence continuing S. $37^{\circ} 48'$ N. 21.70 chains to Monument No. 54 thence S. $75^{\circ} 50'$ N. 3.07 chains, thence S. $116^{\circ} 07'$ N. 12.09 chains to the center of the Union Pacific Railway track, thence S. $36^{\circ} 30'$ N. 9.30 chains, to Monument No. 55, situated near the Riverdale Bridge across Weber River, thence N. $87^{\circ} 10\frac{1}{2}'$ N. 63.43 chains, to Monument No. 56, situated at the intersection of the center of a street four rods in width leading Southward to South Weber District, and being near the Riverdale schoolhouse, thence continuing N. $87^{\circ} 10\frac{1}{2}'$ N. 15.41 chains, thence S. $27^{\circ} 14'$ N. 16.08 chains, to Monument No. 57, situated at the intersection of the center of a street four rods in width leading Westward to Hooper District, thence S. $41^{\circ} 46'$ N. 35.22 chains, thence S. $19^{\circ} 03'$ N. 33.70 chains, thence S. $29^{\circ} 53'$ N. 39.28 chains, to Monument No. 58, at the center of a road four rods in width leading Westward to Hooper, thence continuing S. $29^{\circ} 53'$ N. 4.76 chains, thence due South 55.11 chains, to Monument No. 59, situated on the Southern boundary line of Weber County 50.48 chains N. $52^{\circ} 13\frac{1}{2}'$ E. from the South West corner of the South East Quarter of Section Twenty Three Township Five North of Range Two West, Salt Lake Meridian, The bearing from said monument is to Benchmark Peak N. $12^{\circ} 44'$ E., to Observatory Peak N. $66^{\circ} 04'$ E. The total length of the above road is 376.41 chains from its beginning to this point.

Description of a County Road four rods wide leading Southeastward near the Ogden City Hospital.

40. Beginning at a certain monument of sandstone situated in the center of Main Street near the residence of Robert Burch 23.62 chains West and 26.43 chains S. $37^{\circ} 48'$ N. from the North East corner of the South East Quarter of Section Five Township Five North of Range One West of Salt Lake Meridian designated as Weber County Survey Monument No. 52, the bearing to the lb. S. Observatory being N. $26^{\circ} 42'$ N., and to Observatory Peak N. $84^{\circ} 47'$ E. - running from thence S. $44^{\circ} 31'$ E. 11.50 chains, thence S. $51^{\circ} 19'$ E. 17.37 chains, to the South line of Section Five above named, thence S. $24^{\circ} 11'$ E. 42.93 chains, thence due South 12.69 chains, thence S. $13^{\circ} 51'$ E. 8.21 chains, thence S. $47^{\circ} 35'$ E. 5.89 chains, thence S. $88^{\circ} 5'$ 1.94 chains, thence S. $43^{\circ} 15'$ E. 9.67 chains, to its termination. The bearing to Observatory Peak being N. $69^{\circ} 58'$ E. The length of the above road being 110.20 chains to this point.

Description of a County Road four rods wide leading near the residence of Rufus Allen in Riverdale District.

41. Beginning at a point in the center of Main Street leading Northward to Ogden

County Road Book, ~~V~~

At a session of the County Court of Weber County, in the Territory of Utah, held on the 15th
 day of March A. D. 1897 (the minutes of the proceedings of which are recorded in County Book
1 on page 323 &c.) the following described road was declared to be a Riverdale County Road, to-wit:

In accordance with a recommendation of the County Surveyor, Selectman Shurtliff recommended that owing to an error in the original survey that a portion of the Riverdale County road lying between County Monument No. 48 situated in the center of said road at its intersection with the center line of Washington Avenue, in Ogden City and Weber River Bridge be abandoned and relocated so as to conform as near as possible to existing lines. On motion of Selectman Fay, it was ordered that the recommendations of the committee be adopted and the committee instructed to proceed and have the work done.

Weber County, Utah.

At a session of the County Court of Weber County, in the Territory of Utah, held on the 22nd

day of July A. D. 1899 (the minutes of the proceedings of which are recorded in County Book
 W on page 81 &c.) the following described road was declared to be a County Road, to-wit:

The Ogden Milling and Elevator Company re-
 quested the permission to change the crossing on
 the County Road over the Union Pacific Railroad
 Tracks at Riverdale to a point about 60 feet south of
 the present site, because of the fact that a spur is
 now being built from their mill to the main line of
 the railroad Company. The request was granted.

Weber County, Utah.

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3rd day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book on page 377-8 &c.) the following described road was declared to be a County Road, to-wit:

39. From Ogden through Riverdale to southern Boundary of County. Beginning at a certain monument of sandstone situated in the center of Main Street in the southern part of Ogden City 12.16 chains West and 14.89 chains North from the southeast corner of the northeast quarter of Section No. 5, Township 5 North of Range One West, Salt Lake Meridian, being known and designated as Weber County Monument No. 48 - at the south end of the Weber County Base - the dimensions of said monument are 8" x 8" x 48"; the bearings from said Monument are: to Observatory Peak N. 89° 52' E, to Benlomon Peak N. 2° 08' E, to the spire on the Weber County Court House N. 2° 49' E, and to the U.S. Observatory N. 43° 14' W. running from thence S. 37° 48' W. 45.16 chains, to Monument No. 52, situated at the intersection of

a street four rods wide leading southeastward to the Ogden City Hospital, thence continuing S. 37° 48' W. 42.10 chains to the intersection of the center of a street four rods wide leading westward near the residence of Rufus Allen, thence continuing S. 37° 48' W. 21.70 chains to Monument No. 54, thence S. 75° 50' W. 3.07 chains, thence S. 46° 07' W. 120.9 chains to the center of the U. P. R.R. thence S. 36° 30' W. 9.30 chains to Monument No. 55, situated near the Riverdale Bridge across Weber River, thence N. 87° 10' W. 63.43 chains to Monument No. 56, situated at the intersection of the center of a road, four rods wide leading southward to the South Weber District and being near the Riverdale School House, thence continuing N. 87° 10' W. 15.41 chains, thence S. 27° 4' W. 16.08 chains, to Monument No. 57 situated at the intersection of the center of a street four rods in width leading westward to Hooper District, thence S. 41° 46' W. 35.22 chains, thence S. 19° 03' W. 33.70 chains, thence S. 29° 53' W. 39.28 chains, to Monument No. 58 at the center of a road four rods in width, leading westward to Hooper, thence S. 29° 53' W. 4.76 chains, thence due south 55.11 chains to Monument No. 59, situated on the southern boundary line of Weber County 50.48 chains N. 52° 13½' E. from the southwest corner of the southeast quarter of Section 23, Township 5 North of Range 2 West, Salt Lake Meridian. The bearing to Benlomon Peak is N. 12° 44' E.; to Observatory Peak N. 66° 04' E. The length of the above road is 396.41 chains.