

Record of the County Court of Weber County, Utah Territory.

1885.

March 3.

City 13.84 chains South and 11.45 chains East from the North West corner of Section No. Eight, Township Five North of Range One West Salt Lake Meridian the bearing from said point being as follows: to Observatory Peak N. 80° 43' E, to Benlornond Peak N. 5° 11' E and to Egrie Peak N. 26° 39' E - running from thence N. 73° 30' N. 7.66 chains, thence N. 20° 25' N. 5.39 chains, thence N. 3° 10' E. 12.95 chains, thence N. 2° 50' E. 27.70 chains, thence N. 7° 48' E. 6.02 chains, to the South boundary line of Ogden City Corporation. The bearing to Observatory Peak being N. 87° 58' E, and to Egrie Peak N. 29° 57' E and to Benlornond Peak N. 5° 54' E. The total length of said road being 59.72 chains.

Description of a County Road four rods wide leading Southward in Riverdale District, to South Weber.

42. Beginning at a certain monument of sandstone situated in the center of the Main Street eight rods in width leading Eastward through Riverdale, known and designated as Weber County Survey Monument No. 56 - the bearings from said monument being as follows: to Observatory Peak N. 79° 04' E, to Egrie Peak N. 33° E, to Benlornond Peak N. 10° 22' E, running from thence S. 23° 30' N. 6.46 chains, thence S. 8° 22' N. 11.19 chains, thence S. 1° 25' N. 38.67 chains, thence S. 10° 07' N. 19.57 chains, thence S. 25° 30' E. 18.76 chains, thence S. 34° 29' E. 18.73 chains, thence S. 26° 22' N. 5.42 chains, to a point 6.90 chains due East from the South West corner of Section Eighteen Township Five North of Range One West Salt Lake Meridian, thence continuing S. 76° 22' N. 304 chains, thence S. 38° E. 9.41 chains, thence S. 16° 30' E. 10.78 chains, thence S. 74° E. 22.03 chains, thence S. 8° N. 7.11 chains, thence S. 115° 40' E. 14.12 chains, thence S. 80° E. 10.53 chains, thence S. 211° 58' E. 5.58 chains, to Monument No. 60 situated on the Southern boundary line of Weber County, near South Weber District, with bearings as follows: to Observatory Peak N. 60° 07' E, to Egrie Peak N. 22° 35' E, and to Benlornond Peak N. 6° 14' E. The total length of said road being 204.43 chains.

Description of a County Road part of which is six rods wide, leading from a point near the wagon bridge across the Weber River in Ogden City Westward through Wilson District to West Weber District.

42. Beginning at a certain monument of sandstone situated in the center of the

Record of the County Court of Weber County, Utah Territory.

1885.

March 3.

street 4.37 chains N. 72° 58' W. from the West end of the wagon bridge across Heber River in Ogden City and 99 feet N. 17° 02' E. from the center of the Utah Central Railway track, main line; the bearings from said monument being as follows: to DeLombard Peak N. 8° 17' E. to Signal Peak N. 11° 59' E. and to Observatory Peak S. 71° 11 1/2' E. and to the spire on the Heber County Court House S. 87° 57' E. said monument being known and designated as Heber County Survey Monument No. 61, running from thence N. 50° W. 9.83 chains in the center of a street six rods in width, thence N. 55° W. 8.70 chains in the center of said street, thence N. 70° W. 13.67 chains in the center of a street six rods in width, from which point the road continues four rods in width, thence S. 79° 20' W. 3.58 chains, thence N. 70° W. 5.08 chains, near the residence of Ed Robbins, thence N. 39° 07' W. 6.99 chains, thence N. 85° 56' W. 117.30 chains, thence N. 87° 06' W. 33.51 chains, thence N. 89° 30' W. 31.08 chains, thence North 23.70 chains to a point 5.56 chains South from the North East corner of Section Twenty Six Township Six North of Range Two West, Salt Lake Meridian, thence N. 68° 16' W. 15.47 chains, to the Hooper Drigating Canal, main branch, thence due West 56.21 chains, thence S. 86° 20 1/2' W. 29.48 chains, thence N. 57° 40' W. 3.59 chains, thence N. 89° 53' W. 57.31 chains, to the North West corner of Section Twenty Seven Township Six North of Range Two West of Salt Lake Meridian, thence continuing N. 89° 53' W. 119.85 chains, to a point at the intersection of the center of a road leading from Hooper District North to West Heber and ²⁶/₁₀₀ of one chain due East from the North West corner of the North East Quarter of Section Twenty Nine Township Six North of Range Two West, Salt Lake Meridian. The bearing from said point being: to DeLombard Peak N. 37° 22' E. and to Observatory Peak S. 78° 07' E. The total length of said road is 465.32 chains.

Description of a County Road four rods wide leading Westward from a point near the Utah Central Railway track West from the Observatory at Ogden, to West Heber District.

411. Beginning at a certain monument of sandstone situated 300 chains East from the North West corner of Section No. Thirty One Township Six North of Range One West, Salt Lake Meridian known and designated as Heber County Survey Monument No. 62. - the bearings from said monument being as follows: to Observatory Peak S. 78° 38' E. to DeLombard Peak N. 12° 49 1/2' E. to Signal Peak N. 16° 09' E. running from thence due West on the North line of Sections Thirty Six - Thirty Five - Thirty Four - Thirty Three - and

Weber County, Utah.

At a session of the County Court of Weber County, in the Territory of Utah, held on the 5th
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book
 on page 37980 &c.) the following described road was declared to be a County Road, to-wit:

From Ogden, through Wilson, to West Weber: -

Beginning at a certain monument of sandstone situated in the center of the street 4.37 chains N. $72^{\circ}58'$ W. from the west end of the wagon bridge across Weber River in Ogden City and 99 ft. N. $17^{\circ}02'$ E. from the center of the Utah Central R.R. main line. The bearings from said Monument being as follows: - to Ben Lomond Peak N. $8^{\circ}17'$ E., to Eyrie Peak N. $49^{\circ}59'$ E. and to Observatory Peak S. $74^{\circ}11\frac{1}{2}'$ E. and to the spur of the Weber County Court House, S. $87^{\circ}57'$ E. said Monument being known and designated as Weber County ^{Survey} Monument No. 61, running from thence N. $50^{\circ}01'$ W. 9.83 chains, thence in the center of a street 6 rods in width, thence N. $55^{\circ}01'$ W. 8.70 chains, in the

center of said street, thence N. $70^{\circ}01'$ W. 13.67 chains in the center of a street six rods in width from which point the road continues four rods in width thence S. $79^{\circ}20'$ W. 3.58 chains, thence N. $70^{\circ}01'$ W. 5.08 chains, near the residence of Ed Robbins, thence N. $39^{\circ}01'$ W. 6.99 chains, thence N. $85^{\circ}56'$ W. 47.30 chains, thence N. $87^{\circ}06'$ W. 33.51 chains, thence N. $89^{\circ}30'$ W. 31.08 chains, thence North 23.70 chains, to a point 5.56 chains south from the northeast corner of Section 26, Township 6 North of Range 2 West Salt Lake Meridian, thence N. $68^{\circ}46'$ W. 15.47 chains to Harper Irrigation Canal, main branch, thence due west 56.21 chain, thence S. $86^{\circ}20\frac{1}{2}'$ W. 29.45 chains, thence N. $57^{\circ}40'$ W. 359 chains, thence N. $89^{\circ}53'$ W. 57.31 chain to the Northwest corner of Section 27, Township 6 North of Range 2 West Salt Lake Meridian, thence continuing N. $89^{\circ}53'$ W. 119.85 chains, to a point at the intersection of the center of a road leading from Harper District North to West Weber and 26 of one chain due east from the Northwest corner of the Northeast Quarter of Section 29, Township 6 North of Range 2 West Salt Lake Meridian. The bearing from said point being: to Ben Lomond Peak N. $37^{\circ}22'$ E. and to Observatory Peak S. $78^{\circ}07'$ E. The total length of said road being 465.32 chains.