

Record of the County Court of Weber County, Utah Territory.

1885.

March 3.

Ogden City to Hooper, near the Homeville schoolhouse.

Beginning at a point on the Southern boundary line of Weber County, in the center of the street leading North and South on the East side of Plat "A," Hooper City Survey from which the following bearings were taken: to the South West corner of the North West Quarter of Section Nineteen Township Five North of Range Two West of Salt Lake Meridian N. 30° 00' E. 44.75 chains; to Observatory Peak N. 75° 19' E. to Eyrice Peak N. 119° 58' E. to Benlmonds Peak N. 29° 53½' E. running from thence North in the center of a street four rods in width 15.81 chains to the center of a street leading Eastward near the residence of Henry Manning in Hooper District from which point the following bearings were taken: to Observatory Peak N. 76° 10' E. to Eyrice Peak N. 50° 37½' E. to Benlmonds Peak N. 30° 14½' E. and being near the school house in the Eastern part of Hooper District, continuing thence North 41.34 chains to the intersection of the street leading Eastward to Ogden City; and one rod East of the center of the street six rods in width leading South on the East side of Plat "A," Hooper City Survey, thence North 82.40 chains in the center of a street four rods in width, and to the intersection of a road leading Eastward to the Eastern part of Hooper District, thence continuing North 41.29 chains, thence East 61.41 chains, thence North 3.96 chains, thence East 20.58 chains, thence North 20.51 chains, and to the North West corner of Section Eight, Township Five North of Range Two West, Salt Lake Meridian, thence N. 87° 45' E, on the North line of said section, 40.68 chains, to the center of the street leading North from Hooper to West Weber, thence continuing N. 87° 45' E. 79.06 chains, to the intersection of the center of the road leading from Ogden to Hooper District, and being the South East corner of the South West Quarter of Section Four, Township Five North of Range Two West, Salt Lake Meridian. The bearing to the chimney on the Homeville school-house being N. 85° 24' E. The length of the foregoing road is 407.04 chains.

Description of a County Road four rods wide leading Westward through the Northern part of Hooper District.

Beginning at a point in the center of the street leading Northward from Hooper to West Weber District being 11.49 chains North and $\frac{50}{100}$ of one chain East from the South West corner of the South East Quarter of Section No. Eight, Township Five North of Range

Record of the County Court of Weber County, Utah Territory.

1895.

March 3.

Two West of Salt Lake Meridian, from which the following bearings were taken: to Observatory Peak N. 82° E.; to Egypt's Peak N. 51° 41½' E.; to Benlomonad Peak N. 28° 01' E.; running from thence West 40.77 chains to the center of a street running North & South in the Eastern part of Hooper District; thence continuing West 81.96 chains to the intersection of the center of a street running North and South in the central part of Hooper District; the bearings from this point to Observatory Peak is N. 82° 57½' E. continuing thence West 82.10 chains to the center of a street running North and South near the school house in the Western part of Hooper, thence continuing West 81.90 chains to the center of a street running North and South through the Western part of Hooper and near the Great Salt Lake. This road also runs West to the shore of said Lake. The length of the foregoing road up to the point of intersection is 286.73 chains.

Description of a County Road four rods wide leading Westward through the Southern part of Hooper City to the Great Salt Lake.

50. Beginning at a point in the center of the street leading from Ogden City to Hooper, being 67.80 chains S. 0° 07' N. from the North West corner of the North East Quarter of Section No. Seventeen, Township Five North of Range Two West, Salt Lake Meridian, and on the West line of said quarter section, running from thence due South 41.34 chains, thence West 39.96 chains to the intersection of the center of a street leading Northward in the Eastern part of Hooper, thence continuing West 82.00 chains to the intersection of the center of the street leading Northward through the central part of Hooper, thence West 41.10 chains, in a street six rods in width, one rod South from the center thereof, thence continuing West 41.10 chains in the center of a street four rods in width, and to the intersection of the center of a street running North near the school house of the Western part of Hooper District, thence continuing West 82.20 chains to the intersection of the center of a road leading North in the extreme Western part of Hooper, thence West 23.09 chains to the Eastern shore of the Great Salt Lake, from which point the following bearings were taken: to Observatory Peak N. 78° 17' E. to Egypt's Peak N. 56° 11' E. to Benlomonad Peak N. 36° 46' E. to a monument of stones on Fremont's Island N. 81° 42' N. The total length of the foregoing road is 356.79 chains.

County Road Book,

At a session of the County Court of Weber County, in the Territory of Utah, held on the ^{3rd}
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book
 on page 384-5 &c.) the following described road was declared to be a County Road, to-wit:

Through the northern part of Hooper: -

Beginning at a point in the center of the street leading northward from Hooper to West Weber District being 14.49 chains North and .50 of one chain East from the southwest corner of the southeast quarter of Section 8, in Township 5, North of Range 2 West Salt Lake Meridian, from which the following bearings were taken: to Observatory Peak, N. 82° E.; to Eyrin Peak, N. 51° 41' E.; to Benesmond Peak N. 28° 01' E. running from thence West 40.77 chains to the center of a street running north and south in the Eastern part of Hooper District, thence continuing west 8.96 chains to the intersection of the center of a street running north and south, near the schoolhouse in the western part of Hooper and near the Great Salt Lake. This road also runs west to the shore of said lake. The length of the foregoing road up to the point of intersection is 286.73 chains.

in the central part of Hooper District the bearing to this point from Observatory Peak is N. 82° 57' E. continuing thence 21.82 chains