

Record of the County Court of Weber County, Utah Territory.

1885.

March 3.

Description of a County Road four rods wide leading Northward from Huntsville to
"Middle Fork Canon."

55. Beginning at a certain monument of sandstone, situated in the center of the street leading from Huntsville to "South Fork Canon" being 11.15 chains South of 10.27 chains West from the South East corner of Section Seven, Township Six North of Range Two East, Salt Lake Meridian, known and designated as Weber County Survey Monument No. 99, from which the following bearings were observed: to Observatory Peak S. 55° 31' N. to Benlomonad Peak N. 56° 09' N. and to the spire on the Huntsville meeting-house S. 76° 52½' N. running thence N. 1° 40' N. 102.81 chains, thence N. 20° 5' 38.53 chains, to a point in the mouth of "Middle Fork Canon," from which the following bearings were taken: to Observatory Peak S. 46° 38½' N. to Benlomonad Peak N. 63° 33' N. and to the spire on the Huntsville meeting-house S. 17° 03' N. The length of the foregoing road is 111.34 chains.

Description of a County Road partly six rods and partly four rods wide leading Southward from Huntsville to intersect a road leading to Weber Valley, as follows:

56. Beginning at a certain monument of sandstone situated in the center of the street in Huntsville $\frac{1}{2}$ of one chain North, and $\frac{1}{2}$ of one chain East from the North East corner of Block Thirteen, Plat "A," Huntsville Survey, known and designated as Weber County Survey Monument No. 97, from which the following bearings were observed: to Observatory Peak S. 54° 46' N. to Benlomonad Peak N. 54° 49' N. to the center of the flag-staff on the Public Square S. 43° 34' N. and to the spire on the Huntsville meeting-house N. 83° 54½' N. running from thence S. 1° 25' E. 28.50 chains to Monument No. 98, and in the center of a street six rods in width, thence S. 88° 35' N. 5.40 chains, in the center of a street four rods in width, thence S. 5° N. 7.46 chains, in the center of a street four rods in width, thence S. 1° 25' E. 16.91 chains, thence S. 6° 15' E. 15.54 chains, crossing the main channel of "South Fork," thence S. 9° 15' N. 11.47 chains, thence S. 28° 15' N. 17.54 chains to a point on the foothills South of Huntsville, from which the following bearings were observed: to Observatory Peak S. 62° 35' N. to Benlomonad Peak N. 50° 03' N. and to the spire on the Huntsville meeting-house N. 3° 03' E.

The length of the foregoing road up to this point is

104.82 chains.

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3rd
 day of March A. D. 1895 (the minutes of the proceedings of which are recorded in County Book
 on page 388 &c.) the following described road was declared to be a County Road, to-wit:

55. From Huntsville to Middle Fork Canyon: —

Beginning at a certain monument of sandstone situated in the center of the street leading from Huntsville to South Fork Canyon, being 11.15 chains south and 10.27 chains west from the southeast corner of Section 7, Township 6 North of Range 2 East, Salt Lake Meridian, known and designated as Weber County Survey Monument No. 99, from which the following bearings were observed; to Observatory Peak S. 55° 31' W. to Benlomon Peak N. 56° 09' W. and to the spire on the Huntsville meeting-house, S. 76° 52' W. running thence N. 1° 40' W. 102.81 chains, thence N. 20° E. 38.53 chains, to a point in the Mouth of Middle Fork Canyon, from which the following bearings were taken: to

Observatory Peak, S. 46° 38' W. to Benlomon Peak N. 63° 33' W. and to the spire on the Huntsville meeting-house S. 17° 03' W. The length of the foregoing road is 141.34 chains