

Record of the County Court of Weber County, Utah Territory.

1885

March 3

Township Seven North of Range One East, Salt Lake Meridian, known and designated as Weber County Survey Monument No. 102, running from thence $N. 3^{\circ} E. 22.00$ chains to the North line of the above named Section Twenty Nine, thence $N. 0^{\circ} 32' E. 60.00$ chains to a point 20.66 chains South from the North East corner of the North West Quarter of Section Twenty - of the above Township and Range, and to the intersection of a road leading Southeastward to Eden, thence due West 20.50 chains, thence North 41.95 chains, thence $N. 16^{\circ} 30' W. 23.25$ chains, thence $N. 25^{\circ} 40' W. 30.63$ chains, thence due North 7.76 chains to a point $N. 0^{\circ} 01' W. 01$ chain West and 166 chains South from the North East corner of Section Eighteen, Township Seven North of Range One East, Salt Lake Meridian, thence $N. 54^{\circ} W. 8.25$ chains, thence $N. 48^{\circ} 20' W. 8.55$ chains, thence $N. 37^{\circ} W. 5.18$ chains, thence $N. 42^{\circ} W. 3.23$ chains, to a point near the North Fork of Ogden River from which the following bearings were observed: to Round Peak $N. 81^{\circ} 56' W.$ and to "Cottonwood Peak" $S. 35^{\circ} 33' E.$, thence $N. 35^{\circ} 30' E. 5.37$ chains, crossing the channel of "North Fork" to its Eastern bank. The length of the foregoing road is 236.37 chains.

Description of a County Road four rods wide leading Southward and Eastward from Liberty District, in the North end of Ogden Valley.

63. Beginning at a point in the center of said road 20.66 chains South from the North East corner of the North West Quarter of Section Twenty, Township Seven North of Range One East, Salt Lake Meridian, the bearing to the spire on the Huntsville meeting-house, $S. 44^{\circ} 12' E.$ running from thence due East 9.77 chains, thence $S. 49^{\circ} E. 6.21$ chains, thence $N. 81^{\circ} E. 12.18$ chains, thence $N. 80^{\circ} 52' E. 13.66$ chains, thence East 20.44 chains crossing "North Fork" to its Eastern side, thence $S. 18^{\circ} E. 25.73$ chains, thence $S. 9^{\circ} E. 27.11$ chains, thence $S. 21^{\circ} W. 3.37$ chains, thence $S. 21^{\circ} E. 6.15$ chains, thence $S. 3^{\circ} 30' W. 4.08$ chains, thence $S. 16^{\circ} E. 5.35$ chains, thence $S. 37^{\circ} 30' E. 55.91$ chains, to Monument No. 101, situated at the intersection of the center of the road leading from Eden Northwestward to the Eastern mouth of Ogden Hole Cañon. Bearings are as follows: to the spire on the Huntsville meeting-house $S. 44^{\circ} 21' E.$ and to Cottonwood Peak $S. 35^{\circ} 37' E.$

The length of the foregoing road is 187.95 chains.

County Road Book,

At a session of the County Court of Weber County, in the Territory of Utah, held on the 3rd
 day of March A. D. 1885 (the minutes of the proceedings of which are recorded in County Book
 on page 39^v &c.) the following described road was declared to be a County Road, to-wit:

63.

Southward and Eastward from Liberty: -
 Beginning at a point in the center of said road 70.66 chains south from the ^{Northwest corner of} north West Quarter of Section 20, Township 7 North of Range One East, Salt Lake Meridian; thence bearing to the spire on the Huntsville meeting house $S. 44^{\circ} 12' E.$ running from thence due east 9.79 chains, thence $S. 49^{\circ} E.$ 6.21 chains, thence $N. 81^{\circ} E.$ 12.18 chains, thence $N. 81^{\circ} 52' E.$ 13.66 chains, thence East 20.44 chains crossing North Fork to its eastern side, thence $S. 18^{\circ} E.$ 15.73 chains, thence $S. 9^{\circ} E.$ 27.11 chains, thence $S. 21^{\circ}$ 3.37 chains, thence $S. 21^{\circ} E.$ 6.12 chains, thence $S. 3^{\circ} 30' N. 4^{\circ} 08'$ chains, thence $S. 16^{\circ} E.$ 5.35 chains, thence $S. 37^{\circ} 30' E.$ 55.91 chains, to Monument No.

101, situated at the intersection of the center of the road leading from Eden northwesternward to the Eastern Mouth of Ogden Hole Canyon. Bearings are as follows: - to the spire on the Huntsville meeting house $S. 44^{\circ} 21' E.$ and to Cottonwood Peak $S. 35^{\circ} 27' E.$ The length of the foregoing road is 189.95 chains.