



All of Lot 59, Woodland Estates Subdivision, Unit 3 according to Weber County, Utah according to the official plat thereof.

Lots 59-61 Do Not Close. Lots 57 & 58 close reasonably well. The sides of Lot 59 adjoining 57 & 58 were used as recorded angle H on Lot 60 makes the line between 59 & 60 a radial line, so I held that bearing. The other recorded bearing between 59 & 60 was honored because it was parallel to the rest on the side Lot lines on the street. I then forced the Lot closed between 59 & 60 using the above assumption. The brass Monument and the two found rebars were used for control and basis of bearing.

I, Glenn Ravenberg, Do hereby certify that I am a registered land surveyor, and that I hold certificate No. 3835 as prescribed by the Laws of the State of Utah, and that I made a survey of the above property. I further certify that the above plat correctly show the true dimensions of the property surveyed.

May 11, 194

*Glenn Ravenberg*  
Glenn Ravenberg  
REGISTERED LAND SURVEYOR  
STATE OF UTAH

REC'D  
JUL 01 1944

INTERMOUNTAIN SURVEYING  
Layton, Utah 84041 (801) 544-1170

PROPERTY SURVEY  
FOR  
LANE STROMBERG  
ALL OF LOT 59, WOODLAND ESTATES SUBD. UNIT 3

MAY 11 1944 SCALE 1"=40' PS-94-09