



SURVEYORS CERTIFICATE

I, Larry M. Buttars, a registered Land Surveyor as prescribed by the laws of the State of Utah, and holding licence No. 2596, do hereby certify that I made a survey of the below described property and the Plat hereon is a true and correct representation of said survey.

Date: 3-7-94 Sign: [Signature]



DESCRIPTION PARCEL 1

Part of the S.W. 1/4 of Section 10, T.6N., R.1W., S.L.B. & M., U.S. Survey: Beginning at a point N. 0° 25' 44" E. 534.00 ft. and N. 89° 44' 16" E. 53.0 ft. from the S.W. corner of said 1/4 section, and running thence N. 0° 25' 44" E. 62.00 ft., thence S. 89° 34' 11" E. 130.00 ft., thence S. 0° 25' 44" W. 62.00 ft., thence N. 89° 34' 11" W. 130.00 ft. to the point of beginning. Cont. 8060 Sq. ft.

PARCEL 2

Part of the S.W. 1/4 of Section 10, T.6N., R.1W., S.L.B. & M., U.S. Survey: Beginning at a point N. 0° 25' 44" E. 596.00 ft. and N. 89° 44' 16" E. 33.0 ft. from the S.W. corner of said 1/4 section, and running thence N. 0° 25' 44" E. 21.00 ft., thence S. 89° 34' 11" E. 240.00 ft., thence S. 0° 25' 44" W. 83.00 ft., thence N. 89° 34' 11" W. 110.00 ft., thence N. 0° 25' 44" E. 62.00 ft., thence N. 89° 34' 11" W. 130.00 ft. to the point of beginning. Contains 11,760 Sq. ft.

NARRATIVE

The purpose of this Survey was to divide lot into two parcels for construction of house and obtain Mtg. release on parcel 2. Ogden City bearings and co-ordinates were used for this survey.

LEGEND

- o Set 3/4" x 24" re-bar with plastic cap stamped L. Buttars R.L.S. 2596
- Set P.K. nail with ribbon

RECEIVED

AUG 31 1994

W: [Signature]

BUTTARS SURVEYING	
1815 26 TH STREET	OGDEN, UT. 84401
PHONE	392-5291
CLIENT: MARK WILLIAMS	
SURVEY LOCATION:	
S.W. 1/4 SEC. 10, T.6N., R.1W., S.L.B. & M. OGDEN CITY, WEBER COUNTY	
SURVEY DATE: 3-5-94	