



CENTER OF SEC. 15,  
T5N, R2W, SLB&M  
(FOUND MONUMENT)

N.E. COR. OF SEC. 15,  
T5N, R2W, SLB&M  
(FOUND MONUMENT)

S.E. COR. OF N.E. 1/4  
OF SEC. 15, T5N,  
R2W, SLB&M  
(FOUND MONUMENT)

WAYNE CAMPBELL  
BOUNDARY LINE AGREEMENT  
SOUTH BOUNDARY  
BEGINNING AT A POINT WHICH IS NORTH 0°13'23" EAST 133.58 FT. ALONG THE SECTION LINE FROM THE SOUTHEAST CORNER OF THE NORTHEAST QUARTER OF SECTION 15, T5N, R2W, SLB&M, U.S. SURVEY, RUNNING THENCE NORTH 89°25'29" WEST 440.54 FT. ALONG AN EXISTING FENCE AND FENCE EXTENDED TO THE EAST LINE OF THE RAIL ROAD RIGHT OF WAY.

WAYNE CAMPBELL  
BOUNDARY LINE AGREEMENT  
NORTH BOUNDARY  
BEGINNING AT A POINT WHICH IS NORTH 0°13'23" EAST 193.58 FT. ALONG THE SECTION LINE FROM THE SOUTHEAST CORNER OF THE NORTHEAST QUARTER OF SECTION 15, T5N, R2W, SLB&M, U.S. SURVEY, RUNNING THENCE NORTH 89°25'29" WEST 440.54 FT. PARALLEL TO AND 60.00 FT. NORTH OF AN EXISTING FENCE AND FENCE EXTENDED TO THE EAST LINE OF THE RAIL ROAD RIGHT OF WAY.

EXISTING DEED  
A PART OF THE NORTHEAST QUARTER OF SECTION 15, T5N, R2W, SLB&M, U.S. SURVEY, BEGINNING AT A POINT WHICH IS NORTH 0°13'23" EAST 126.00 FT. ALONG THE SECTION LINE FROM THE SOUTHEAST CORNER OF THE NORTHEAST QUARTER OF SAID SECTION 15, THE SOUTHEAST CORNER OF THE NORTHEAST QUARTER OF SAID SECTION 15, AND RUNNING THENCE NORTH 89°38'02" WEST 440.10 FT. TO THE EAST RIGHT OF WAY LINE OF THE RAIL ROAD RIGHT OF WAY, THENCE NORTH 2°28'37" WEST 60.07 FT., THENCE SOUTH 89°38'02" EAST 442.93 FT. TO THE SECTION LINE, THENCE SOUTH 0°13'23" WEST 60.00 FT. TO THE POINT OF BEGINNING.

CONTAINS 0.608 ACRES

NARRATIVE  
THIS SURVEY WAS DONE TO DEFINE THE PROPERTY LINE PRIOR TO CONSTRUCTION OF A BUILDING. THE THREE SECTION CORNERS SHOWN WERE LOCATED AND USED FOR SURVEY CONTROL AND BASIS OF BEARINGS. WHEN THE OCCUPATION LINES WERE FOUND TO BE SO FAR OFF BOUNDARY LINE AGREEMENT DESCRIPTIONS WERE PREPARED TO CORRECT THE DIFFERENCES.

I, GLENN RAVENBERG, DO HEREBY CERTIFY THAT I AM A REGISTERED LAND SURVEYOR, AND THAT I HOLD CERTIFICATE NO. 3835 AS PRESCRIBED BY THE LAWS OF THE STATE OF UTAH, AND THAT I HAVE MADE A SURVEY OF THE ABOVE DESCRIBED PROPERTY. I FURTHER CERTIFY THAT THE ABOVE PLAT CORRECTLY SHOWS THE DIMENSIONS OF THE PROPERTY SURVEYED.

MAY 31, 1994

*Glenn Ravenberg*  
GLENN RAVENBERG

INTERMOUNTAIN SURVEYING  
Layton Utah 84041 (801) 544-1170

PROPERTY SURVEY FOR  
WAYNE CAMPBELL  
PART OF THE N.E. 1/4 OF SEC. 15, T5N, R2W

MAY 23, 1994 1"=40' PS-94-42