



NARRATIVE:
This Survey was requested by Mr. Gary Crampton for the purpose of establishing the boundaries of the property and North 1/4 corners of Section 28, 17N, R1E. A line bearing $N 00^{\circ}55'00'' W$ between this two monuments was used as the basis of bearings. Property corners were monumented as depicted on this drawing.

Contains 5.225 Acres

EAGLE'S VIEW SUBDIVISION

DESCRIPTION

A part of the Southwest Quarter of Section 28, Township 7 North, Range 1 East, Soil Lake Base and Meridian, U.S. Survey. Beginning of a point which is 591.38 feet North $0^{\circ}55'00''$ West along the Quarter Section Line from the South Quarter Corner of said Section 28; running thence South $0^{\circ}55'00''$ East 237.13 feet; thence due West 847.79 feet to the center of an existing road; thence North $5^{\circ}01'00''$ East 310.00 feet along the center of said road; thence South $84^{\circ}59'00''$ East 820.06 feet (820.03 feet to close) to the place of beginning.

CERTIFICATION

I, Jay R. Anderson, do hereby certify that I am a Registered Land Surveyor, and that I hold Certificate No. 4350, the above described property, I further certify that the above plat correctly shows the true dimensions of the property surveyed.

Jay R. Anderson

Date: 9-27-95



Property Survey
A part of the Southwest 1/4 of Section 28, 17N, R1E, S18 & M.

GARY CRAMPTON
Gary Crampton
20 Wendy Drive Home and Garden
Liberty, Weber County, Utah

GREAT BASIN ENGINEERING, INC.
GREAT BASIN ENGINEERING, INC.
2544 Lincoln Avenue, Ogden, Utah, 84401
P.O. Box 2075 Ogden, Utah, 84401
Phone: (801) 231-1111 Fax: (801) 231-1111

SCALE: 1" = 40'
DATE: 6 Oct. 1995
SHEET: 1 of 1
PROJECT: 95-42
JOB NO: PS-95-42

RECEIVED
SEP 28 1995
JERRY D.