



LEGAL DESCRIPTION

A PART OF LOTS 2 AND 3 OF BLOCK 9, PLAT A, HOOPER CITY SURVEY, IN THE NORTHEAST QUARTER OF SECTION 24, TOWNSHIP 5 NORTH, RANGE 3 WEST, SALT LAKE BASE AND MERIDIAN, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGINNING AT A POINT ON THE WEST LINE OF SAID BLOCK 9, AT A POINT S. 0° 58' 30" W. (S. 0° 28' W.) 107.71 FEET FROM THE NORTHWEST CORNER OF SAID LOT 3, SAID POINT ALSO BEING N. 89° 28' 31" W. (N 89° 58' W) 778.21 FEET ALONG SECTION LINE (BASIS OF BEARINGS) AND S. 0° 58' 30" W. (S. 0° 28' W.) 189.37 FEET FROM THE NORTHEAST CORNER OF SAID SECTION 24 (AS MONUMENTED); AND RUNNING THENCE S. 89° 01' 51" E. 154.50 FEET, THENCE S. 0° 58' 30" W. 129.42 FEET TO A FENCE, THENCE N. 89° 14' 12" W. 154.50 FEET ALONG SAID FENCE TO THE WEST LINE OF SAID BLOCK 9, THENCE N. 0° 58' 30" E. (N. 0° 28' E.) 130.00 FEET TO THE POINT OF BEGINNING. CONTAINING 20,040 SQUARE FEET, MORE OR LESS.

SURVEYOR'S CERTIFICATE

I, CHESTER L. NELSON DO HEREBY CERTIFY THAT I AM A REGISTERED LAND SURVEYOR, AND THAT I HOLD CERTIFICATE No. 4263 AS PRESCRIBED BY THE LAWS OF THE STATE OF UTAH, AND THAT I HAVE MADE A SURVEY ON THE GROUND, AND FROM RECORDS OF THE WEBER COUNTY RECORDERS OFFICE AND AS DESCRIBED ABOVE AND SHOWN PER THIS PLAT.

5-23-89  
DATE

*Chester L. Nelson*  
CHESTER L. NELSON  
R.L.S. No. 4263

NARRATIVE

THE PURPOSE OF THIS SURVEY WAS DONE TO CREATE A PARCEL OF LAND FOR CHERIE LOFTUS FOR A ONE LOT SMALL LOT SUBDIVISION. BASIS OF BEARINGS BEING N. 89° 28' 31" W. ALONG THE SOUTH LINE OF SECTION 13, (AS MONUMENTED) TOWNSHIP 5 NORTH, RANGE 3 WEST, SALT LAKE BASE AND MERIDIAN, FOUND CONCRETE MONUMENT AT THE NORTHEAST CORNER OF 5900 WEST AND 5900 SOUTH AND AT THE NORTHWEST CORNER OF 6700 WEST AND 5500 SOUTH PER OFFICIAL MAP OF HOOPER.



LEGEND

- o SET 5/8" REBAR W/SURVEY CAP No. 4263.
- SET 1/2" REBAR W/SURVEY CAP No. 4263.
- x-x-x-x-x EXISTING FENCE.
- ( ) DISTANCE AND OR BEARING PER DEED OR PLAT.
- NO PARENTHESSES IS MEASURED DISTANCE OR ROTATED PLAT OR DEED BEARING TO STATE PLANE GRID BEARING.

RECEIVED

MAY 23 1989

Weber County Surveyor

NELSON SURVEYING 1500 N. 5900 W. OGDEN, UTAH 84404 (801) 731-1131	
CLIENT:	CHERIE LOFTUS
SURVEY LOCATION:	N.E. 1/4 SECTION 24, TOWNSHIP 5 NORTH, RANGE 3 WEST, SALT LAKE BASE & MERIDIAN.
SURVEY DATE:	4-10-89
JOB No.	P.S.89-05