



RECORD OF SURVEY FOR
BARLOW CORPORATION
 PART OF THE SOUTH HALF OF SECTION 9, TOWNSHIP 5 NORTH,
 RANGE 2 WEST, OF THE SALT LAKE BASE AND MERIDIAN,
 WEST HAVEN, WEBER COUNTY, UTAH
 MAY, 2002

DESCRIPTION

PART OF THE SOUTH HALF OF SECTION 9, TOWNSHIP 5 NORTH, RANGE 2 WEST, SALT LAKE BASE & MERIDIAN, COMMENCING AT THE SOUTHWEST CORNER OF SAID SECTION 9, BEING THE INTERSECTION OF THE WEST LINE OF SAID SECTION 9, NORTH 00°42'44" EAST ALONG THE EAST LINE OF SAID SECTION 9, 2963.86 FEET (NORTH 00°20'15" WEST, 2966.81 FEET BY RECORD); THENCE NORTH 89°15'01" WEST (WEST BY RECORD), 15.84 FEET AND SOUTH 89°42'29" WEST, 24.08 FEET TO THE EAST LINE OF REGAL PHASE II; THENCE ALONG REGAL COUNTRY ESTATES PHASE I, LOT 24 THE FOLLOWING TWO COURSES: (1) SOUTH 89°42'29" WEST, 68.74 FEET (SOUTH 89°00'30" WEST, 70.11 FEET BY RECORD); (2) SOUTH 89°15'01" WEST, 15.84 FEET TO THE SOUTHWEST CORNER OF SAID REGAL COUNTRY ESTATES PHASE I, LOT 24 AND A FOUND REEVE'S SURVEY MARKER AND ON THE WEST RIGHT-OF-WAY LINE OF THE LATON CANAL TO THE TRUE CANAL AND EXISTING FENCE THE FOLLOWING TWO COURSES: (1) SOUTH 00°27'01" WEST, 481.58 FEET (SOUTH 00°18'30" WEST, 453.86 FEET BY RECORD); (2) SOUTH 29°24'30" WEST, 310.00 FEET BY RECORD TO EXISTING FENCE CORNER; THENCE NORTH 89°19'07" EAST ALONG EXISTING FENCE, SAID FENCE BEING THE WEST RIGHT-OF-WAY LINE OF THE LATON CANAL TO THE EAST BOUNDARY LINE OF LONGHORN SUBDIVISION, COMMON AREA AND MO. 14, 2376.55 FEET (WEST, 2381.00 FEET BY RECORD) TO THE EAST BOUNDARY LINE OF REGAL COUNTRY ESTATES, PHASE 2; THENCE ALONG THE SOUTH BOUNDARY LINES OF REGAL COUNTRY ESTATES PHASE I AND PHASE II TO REEVE'S SURVEY MARKERS SOUTH 89°15'01" EAST, 254.34 FEET (EAST, 254.00 FEET BY RECORD) TO THE POINT OF BEGINNING, CONTAINING 43.56 ACRES.

I, WAYNE L. CROW, DO HEREBY CERTIFY THAT THIS IS A TRUE AND ACCURATE REPRESENTATION OF THE SURVEY MADE BY ME AND MY ASSISTANTS, AND SAID SURVEY IS IN ACCORDANCE WITH THE STATUTES THEREON.

Wayne L. Crow
 WEBER COUNTY LICENSE NO. 91102
 JUNIOR LEVEL SURVEYOR

NO.	REVISION	DATE

This document and the ideas incorporated herein, as an instrument of professional service, are the property of Knighton and Crow, P.C. and shall remain their property or in their possession, for any other project without the written authorization of an authorized representative of Knighton and Crow, P.C. Any reproduction or use will be prosecuted to the fullest extent of the law.

Copyright © 1987 KNIGHTON AND CROW, P.C.

Project Title:
BARLOW SUBDIVISION
 WEST HAVEN, WEBER COUNTY, UTAH

Sheet Title:
RECORD OF SURVEY

Knighton and Crow, P. C.
 ONE AND STRUCTURAL ENGINEERING - ARCHITECTURE

81 West 92nd Street, Suite 200, Salt Lake City, UT 84143 (801) 955-8507

Drawn By: S. HARRIS	Project Number: 88-188	Sheet No.:
Designed By: W. CROW	Date: 02/04/02	C1
Reviewed By:	Sheet Scale: 1" = 100'	
File Name: 88-188/RECORD-OF-SURVEY.DWG		

- SURVEY NARRATIVE**
1. BASIS OF BEARINGS FOR THIS SURVEY IS NORTH 00°42'44" EAST ALONG THE EAST LINE OF THE SOUTHWEST QUARTER OF SECTION 9.
 2. THE PURPOSE OF THIS SURVEY IS TO DIVIDE THE SUBJECT PROPERTY (RECORDED AT BOOK 8 PAGE 50-52, WEBER COUNTY RECORDERS OFFICE) TO LOTS AND STREETS AS SHOWN.
 3. RETRACEMENT: NORTH LINE AT SOUTH LINE OF REGAL COUNTRY ESTATES SUBDIVISIONS PHASES I, II & III AND FOUND REEVE'S SURVEY MARKERS, SOUTH LINE AT NORTH LINE OF FOXBLLEN SUBDIVISION, COMMON AREAS AND 1 THRU MO. 14, EAST LINE AT WEST RIGHT-OF-WAY LINE OF CANAL.
 4. 5/8" REBAR CAPS TO BE PLACED ON PROPERTY CORNERS OF SUBDIVISION.

LEGEND

- SECTION CORNER
- SET MARKER
- FOUND MARKER
- FENCE
- CURB CUTTER & SIDEWALK
- PAVEMENT
- PUBLIC UTILITY EASEMENT
- BOUNDARY LINE
- ADJACENT PROPERTY LINE
- CORPORATE LIMIT LINE
- EDGE OF ASPHALT
- DITCH / CANAL
- FLOWLINE
- SECTION LINE

RECEIVED
 MAY 01 2002
 Weber County Surveyor