



RECEIVED
 MAR 22 2005
 Weber County Surveyor

Narrative
 The purpose of this survey was to establish and set the property corners of the parcel as shown and described hereon. The survey was ordered by Brent Slater of Jones and Associates Engineering for Harrisville City. The control used to establish the property corners was the existing Weber County Survey Monumentation surrounding Section 6, T6N, R1W, SLB&M. The basis of bearing is the North line of the northeast quarter of said Section assumed to bear N 89°46'34" E as currently monumented.

As Surveyed Description

A PART OF THE NORTHEAST AND SOUTHEAST QUARTERS OF SECTION 6, TOWNSHIP 6 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN.
 BEGINNING AT A BRASS CAP MONUMENT BEING A POINT LOCATED 845.98 FEET (849.0 FEET RECORD) NORTH 89°46'34" EAST ALONG THE NORTH LINE OF SAID NORTHEAST QUARTER AND SOUTH 00°00'00" EAST 483.48 FEET (458.90 FEET RECORD) FROM THE NORTHWEST CORNER OF SAID NORTHEAST QUARTER; RUNNING THENCE SOUTH 00°17'38" WEST 290.01 FEET ALONG AN EXISTING FENCE LINE; THENCE NORTH 89°55'42" WEST 822.56 FEET ALONG AN EXISTING FENCE LINE TO THE EAST RIGHT-OF-WAY LINE OF 750 WEST STREET; THENCE NORTH 00°32'18" EAST 569.39 FEET ALONG SAID EAST RIGHT-OF-WAY LINE; THENCE NORTH 89°46'34" EAST 257.40 FEET; THENCE NORTH 00°32'18" EAST 150.00 FEET TO THE NORTH LINE OF SAID NORTHEAST QUARTER; THENCE NORTH 89°46'34" EAST 558.71 FEET (558.6 FEET RECORD) ALONG SAID NORTH LINE; THENCE SOUTH 00°23'23" WEST 483.51 FEET ALONG AN EXISTING FENCE LINE TO THE POINT OF BEGINNING.
 CONTAINING 12.88 ACRES.

- LEGEND:**
- PROPERTY LINE
 - CENTERLINE
 - EDGE OF PAVEMENT
 - - - DITCH
 - - - FENCE LINE
 - FOUND BRASS CAP MONUMENT
 - SET 5/8" REBAR W/ CAP SET 01/0705

SURVEY CERTIFICATE

I, K. Greg Hansen, do hereby certify that I am a Registered Land Surveyor, and that I hold Certificate No. 167819 as prescribed by the Laws of the State of Utah, and that I have made and/or Supervised the survey of the property shown and described hereon and that this plot is a true and correct representation of said survey to the best of my knowledge and belief.

K. Greg Hansen, RLS. No. 167819
 K. GREG HANSEN
 STATE OF UTAH
 167819
 date 3/11/2005

JAH HANSEN & ASSOCIATES, INC. Consulting Engineers and Land Surveyors 538 North Main Brigham City, Utah 84302 Brigham City Ogden Logan (435)723-3481 (801)398-4905 (435)752-8272	
Drawn By: <u>John</u> Date: <u>01/05/05</u> Checked By: _____ Approved By: _____ Scale: 1" = 100' Drawing File: <u>02-3-3.dwg</u> JOB NUMBER: <u>02-3-3</u>	PROPERTY SURVEY FOR Harrisville City ± 1730 North 750 West Harrisville, Weber County, Utah A PART OF THE NE QUARTER OF SECTION 6, TOWNSHIP 6 NORTH, RANGE 1 WEST, S.L.B.& M.
SHEET 1 OF 1 SHEETS	003443