

WEBER COUNTY MONUMENT
BRASS CAP IN PIPE
STAMPED
BOX ELDER-WEBER 1990

WEBER COUNTY MONUMENT
BRASS CAP SET IN LARGE
BOULDER, STAMPED
BOX ELDER-WEBER 1990

BOX ELDER COUNTY

WEBER COUNTY

WADMAN INVEST
160040005

WELL SITE
1.6 Acres

Basis of Bearing
N55°06'51"E 422.82'

S07°20'28"E 372.81'

N72°01'57"W

414.69'

NORTH 586.95'

JOSEPH C JENSEN
& BESSY JENSEN
160040006
5.8 AC±

JESSIE CREEK WELL SITE DESCRIPTION

BEING A PART OF THE SOUTHEAST QUARTER OF SECTION 7, TOWNSHIP 7 NORTH,
RANGE 1 WEST, SALT LAKE BASE AND MERIDIAN,
BEGINNING AT A POINT ON THE WEBER, BOX ELDER COUNTY LINE SAID POINT
BEING N.89°47'17"W. 1332.38 FEET AND NORTH 586.95 FEET FROM THE
SOUTHEAST CORNER OF THE SOUTHEAST QUARTER OF SAID SECTION 7, AND
RUNNING; THENCE, N.55°06'51"E., ALONG THE COUNTY LINE, 422.82 FEET; THENCE,
S.7°20'28"E. 372.81 FEET; THENCE, N.72°01'57"W. 414.69 FEET TO THE POINT OF
BEGINNING. CONTAINING 1.6 ACRES, MORE OR LESS.

NARRATIVE AND STATEMENT OF PURPOSE

AT THE REQUEST OF THE PLEASANT VIEW CITY ENGINEER A SURVEY OF THE
SITE WAS PERFORMED THE PURPOSE OF WHICH WAS TO ESTABLISH THE
BOUNDARY OF A PARCEL OF LAND FOR THE LOCATION OF A NEW WELL. THE
LOCATION AND DIMENSIONS OF THE ACTUAL BOUNDARY WERE PROVIDED BY
THE PLEASANT VIEW CITY ENGINEER. MONUMENTS FOUND ON THE COUNTY
LINE AND WEBER COUNTY SECTION CORNER MONUMENTS WERE UTILIZED TO
THIS END. THE BASIS OF BEARING WAS THE MONUMENTED COUNTY LINE.

WEBER COUNTY MONUMENT
SOUTHEAST CORNER
SECTION 7, T.7 N., R.1 W.

SECTION LINE

N89°47'17"W

1332.38'

WILLIAM W WHITE
& WF DONNA R
160120031
22.14 AC±


JOSEPH JAMES & WF PHOEBE
160120042 5.22 AC

MINDY LEE
SCOTT
160120041
5.04 AC±

JESSIE-CREEK-DRIVE

- LEGEND:
- DENOTES A SET #5 CAPPED REBAR
24" LONG
 - DENOTES A FOUND CAPPED REBAR
 - ◆ DENOTES A MONUMENT

CAP DETAIL



SURVEYOR'S CERTIFICATE
I, DICK N. MECHEM, DO HEREBY CERTIFY THAT I AM A PROFESSIONAL LAND SURVEYOR OF
THE STATE OF UTAH, HOLDING LICENSE NUMBER 155649 AND THAT THIS MAP IS A TRUE
AND COMPLETE REPRESENTATION OF A SURVEY MADE BY ME, OR UNDER MY SUPERVISION,
AT THE REQUEST OF PLEASANT VIEW CITY CORP. AND IN BEHALF OF MTWEST SURVEYING &
MAPPING, INC. ALL MONUMENTS SHOWN HEREON ARE OF THE CHARACTER AND OCCUPY THE
POSITIONS INDICATED, AND ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.



Nov 15, 2004
DATE

RECEIVED
MAR 30 05
Weber County Survey
003448

RECORD OF SURVEY
for
PLEASANT VIEW CITY CORP.
JESSIE CREEK WELL SITE

Located in The Southeast One-Quarter Of Section 7,
Township 7 North, Range 1 West, S.L.B.&M.

Date: Nov. 2004	No. 16G-01-03	Drawn: DNM	Ch'g: JJH
MtnWest Surveying & Mapping, Inc.		1825 W. 4400 S. Roy, Utah 84067	PO Box 207 84067 Phone: (801) 731-5330 Fax: (801) 731-5331