



SCALE: 1" = 100'
 ● = REBAR & CAP

NE COR SEC 8,
 T.6 N. R.2 W. S.L.B & M
 W.C. 3" B.C.



I, DOUG GRAHAM, A REGISTERED LAND SURVEYOR AS REQUIRED BY THE LAWS OF THE STATE OF UTAH, AND HOLDING LICENSE NO. 8009, HEREBY CERTIFY THAT I HAVE MADE A SURVEY OF THE BELOW DESCRIBED PROPERTY AND THE PLAT HEREON IS A TRUE AND CORRECT REPRESENTATION OF SAID SURVEY.

DATE: 5/22/90 SIGNED: *Doug Graham*

PARCEL A

PART OF THE NORTH EAST QUARTER OF SECTION 8, TOWNSHIP 6, NORTH, RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN: BEGINNING AT A POINT NORTH 89°30'43" WEST 966.23 FEET FROM THE NORTH EAST CORNER OF SAID SECTION 8 AND RUNNING THENCE SOUTH 0°44'23" WEST 561.00 FEET, THENCE SOUTH 89°28'28" EAST 53.60 FEET, THENCE SOUTH 0°44'23" WEST 429.0 FEET TO THE NORTH RIGHT OF WAY OF 950 NORTH STREET, THENCE NORTH 89°28'28" WEST 150.0 ALONG SAID NORTH RIGHT OF WAY, THENCE NORTH 0°42'49" EAST 429.0 FEET, THENCE NORTH 89°28'28" WEST 254.50 FEET, THENCE NORTH 0°45'35" EAST 560.73 FEET TO THE QUARTER SECTION LINE, THENCE SOUTH 89°30'43" EAST 350.90 FEET TO THE POINT OF BEGINNING.

CONTAINS 6.0 ACRES

PARCEL B

PART OF THE NORTH EAST QUARTER OF SECTION 8, TOWNSHIP 6, NORTH, RANGE 2 WEST, SALT LAKE BASE AND MERIDIAN: BEGINNING AT A POINT NORTH 89°30'43" WEST 654.06 FEET FROM THE NORTH EAST CORNER OF SAID SECTION 8 AND RUNNING THENCE SOUTH 0°44'23" WEST 468.60 FEET, THENCE SOUTH 89°08'15" WEST 19.60 FEET, THENCE SOUTH 0°44'23" WEST 521.13 FEET TO THE NORTH RIGHT OF WAY OF 950 NORTH STREET, THENCE NORTH 89°28'28" WEST 239.0 FEET ALONG SAID NORTH RIGHT OF WAY, THENCE NORTH 0°44'23" EAST 429.0 FEET, THENCE NORTH 89°28'28" WEST 53.60 FEET, THENCE NORTH 0°44'23" EAST 561.0 FEET, THENCE SOUTH 89°30'43" EAST 312.17 FEET TO THE POINT OF BEGINNING.

CONTAINS 6.33 ACRES

E. 1/4 COR. SEC. 8,
 T.6 N. R.2 W. S.L.B & M
 W.C. 3" BRASS CAP

NARRATIVE

THE PURPOSE OF THIS SURVEY WAS TO DIVIDE A PARCEL OF PROPERTY INTO TWO PARCELS. A RECENT SURVEY FOR THE WEST WEBER CEMETARY WAS MATCHED ON THE WEST SIDE ADJOINING THIS PROPERTY, THE NORTH RIGHT OF WAY OF 950 NORTH STREET WAS ALSO MATCHED FROM THE SAME SURVEY.

RECEIVED
 JUL 27 1990

Weber County Surveyor

LANDMARK SURVEYING		825-3187
		771-5144
CLIENT:	ROBERT PENMAN	
SURVEY LOCATION	N.E. 1/4 SEC. 8, T.6 N. R.2 W. S.L.B & M WEST WEBER, UTAH	
SURVEY DATE	MAY 19, 1990	