



SURVEYOR'S CERTIFICATE

I, Larry M. Buttars, a registered Land Surveyor as prescribed by the laws of the State of Utah, and holding License No. 2596, do hereby certify that I made a survey of the below described property and the plat hereon is a true and correct representation of said survey.

Date 1-29-91 Sign *Larry M. Buttars*

I also certify that the Well and Septic tank for the existing house are located within the described parcel 1.

DESCRIPTION

PARCEL 1

Part of the N.E. 1/4 of Section 9, T. 6 N., R. 1 W., S.L.B. & M., U.S. Survey; Beginning at a point S. 0°29'55" W. 924.0 ft. along the section line from the N.E. cor. of said Section 9, and running thence S. 0°29'55" W. along said Section line 198.0 ft., thence N. 89°02'10" W. 867.57 ft. to East line of Mt. Road, thence N. 8°47'20" E. 196.31 ft., thence S. 89°16'30" E. 839.24 ft. to the point of beginning. ALSO: Beginning at a point S. 0°29'55" W. 1122.0 ft. and N. 89°02'10" W. 542.57 ft. from the N.E. corner of said Section 9, and running thence S. 10° W. 104. ft., thence N. 89°02'10" W. 15 ft., thence N. 10° E. 104.0 ft., thence S. 89°02'10" E. to the point of beginning. Cont. 3.92 AC.

PARCEL 2

Part of the N.E. 1/4 of Section 9, T. 6 N., R. 1 W., S.L.B. & M., U.S. Survey; Beginning at a point S. 0°29'55" W. 1122.0 ft. from the N.E. corner of said section 9, and running thence S. 0°29'55" W. 198.0 ft. along the section line, thence N. 89°02'10" W. 896.39 ft. to the East line of Mt. Road, thence N. 8°47'20" E. 199.85 ft., thence N. 89°02'10" E. 310.0 ft., thence S. 10°00' W. 104.0 ft., thence S. 89°02'10" E. 15 ft., thence N. 10°00' E. 104.0 ft., thence S. 89°02'10" E. 542.57 ft. to the point of beginning. Cont. 3.97 AC.

LEGEND

- Set 1/2" x 24" re bar with plastic cap stamped L. Buttars R.L.S. 2596
- Set 1/2" x 24" re bar with cap

RECEIVED

APR 2 1991

Weber County Surveyor

BUTTARS SURVEYING

1815 26th STREET OGDEN, UT. 84401
PHONE 392-5291

CLIENT: SHARRON WILLIAMS

SURVEY LOCATION:
N.E. 1/4 SEC. 9, T. 6 N., R. 1 W., S.L.B. & M.
WEBER COUNTY, UTAH

SURVEY DATE: 1-29-91