



SCALE: 1" = 40'

NOTE:  
 DEED BEARINGS ROTATED 0°10'25"  
 COUNTER CLOCKWISE TO MATCH SECTION  
 LINE BEARING.  
 ONLY THE FRONT CORNERS WERE  
 SET AT OWNERS REQUEST.  
 SECTION LINE INFO & TIES TO STREET  
 MONUMENTS TAKEN FROM OGDEN CITY  
 ENGINEERING PLATS.

CONTAINS 0.92 ACRES

A part of the South half of Section 8, T6N, R1W, SLB&M, U.S. Survey; beginning at a point which is North 0°01'25" West 1561.42 feet along the quarter Section Line from the Southeast corner of the Southwest quarter of Section 8, T6N, R1W, SLB&M, U.S. Survey; running thence South 89°58'35" West 279.80 feet to the East line of Wall Avenue, thence North 0°58' East 75.00 feet along said East line, thence North 89°58'35" East 150.00 feet, thence North 0°58' East 70.00 feet, thence North 89°58'35" East 100.00 feet, thence South 0°01'25" East 75.00 feet, thence North 89°58'35" East 206.70 feet, thence South 0°01'25" East 69.99 feet, thence South 89°58'35" West 178.11 feet to the point of beginning.

Containing 0.92 Acres

I, Glenn Ravenberg, do hereby certify that I am a registered Land Surveyor, and that I hold certificate No. 3835, as prescribed by the Laws of the State of Utah, and I have made a survey of the above described property. I further certify that above plat correctly shows the true dimensions of the property surveyed.

*Glenn Ravenberg*  
 GLENN RAVENBERG

HARRISVILLE ROAD  
 FOUND OGDEN CITY MON.

508  
 RECEIVED  
 JAN 25 1991  
 Weber County Surveyor

<b>INTERMOUNTAIN SURVEYING</b>		
Layton, Utah 84041	(801) 544-1170	
PROPERTY SURVEY FOR DOROTHY POULK		
PART OF SQ. 1/2 OF SEC. 8, T6N, R1W, SLB&M		
JUNE 8, 1989	1" = 40'	PS = 89 = 53