



SCALE 1" = 30'

NOTE: Rebar are 3/8" dia. - 24" long. • with cap reading ARAVE SURVEYING.

Original Deed Description

Part of the Northwest Quarter of Section 21, Township 6 North, Range 2 West, Salt Lake Base & Meridian, U.S. Survey: Beginning at a point 20 Rods and 15.75 feet South and 40 Rods West and South 834.75 feet and West 30 Rods from the Northeast Corner of said Quarter Section and running thence North 169 feet, thence East 221 feet, thence South 169 feet, thence West 221 feet to the point of beginning.

Actual Description

Part of the Northwest Quarter of Section 21, Township 6 North, Range 2 West, Salt Lake Base & Meridian, U.S. Survey: Beginning at a point N 89° 15'33" W 1032.99 feet and S 0°44'27" W 811.49 feet from the Northeast Corner of said Quarter Section and running thence S 0°44'27" W 169.00 feet, thence N 89°15'33" W 221.00 feet, thence N 0°44'27" E 169.00 feet, thence S 89°15'33" E 221.00 feet to the point of beginning.

Surveyor's Certificate

I, Kent G. Arave, a Registered Land Surveyor as prescribed by the laws of the State of Utah and holding License No. 2878, do hereby certify that I have made a Survey of the above described Property and that the Plat hereon is a true and correct representation of said Survey.

Date 9-22-87 Signature Kent G. Arave

Narrative

The purpose of this Survey is to establish the actual Deed Lines in order to construct fences. The basis of bearing was established from the County Grid Data between the existing Section Corners across the North Line of the Northwest Quarter of Section 21.

RECEIVED  
JAN 20 1988  
Weber County Surveyor

PROPERTY SURVEY  
for  
DANIEL J. ROSE  
PART OF NW 1/4 SEC. 21, T6N, R2W  
WEST WEBER DISTRICT, UTAH

Surveyed Sept. 17, 1987

ARAVE SURVEYING  
3918 Riverdale Rd.  
Ogden, Utah Ph. 231-5600