



SURVEYORS CERTIFICATE

I, Larry M. Buttars, a registered Land Surveyor as prescribed by the laws of the State of Utah, and holding licence No. 2596 do hereby certify that I made a survey of the below described property and the Plat hereon is a true and correct representation of said survey.

Date 5-14-92 Sign *Larry M. Buttars*

DESCRIPTION

Beginning at a point N. 89° 14' 53" W. along the Section line and S. 0° 45' 01" W. 30.0 ft. from the N. E. corner of Section 22, T. 5 N., R. 1 W., S.L.B. & M., said point being on the South line of Combe Road; and running thence S. 89° 14' 53" E. 110.14 ft., thence S. 0° 52' 59" W. 90.00 ft., thence N. 89° 14' 53" W. 110.14 ft., thence N. 0° 52' 59" E. 90.00 ft. to the point of beginning.

NARRATIVE

The purpose of this Survey was to establish lot corners for Occupation, State plane Grid bearings from W.C. Surveyor. Deed bearings rotated to State plane Grid. (0° 45' 01" clockwise)

LEGEND

- Set 3/4" x 24" re-bar with plastic cap stamped L. Buttars R.L.S. 2596
- Set P.K. nail with ribbon

BUTTARS SURVEYING
1815 26TH STREET OGDEN, UT. 84401
PHONE 392-5291

CLIENT: DENNIS CLONTZ

SURVEY LOCATION:
N. E. 1/4 SEC. 22, T. 5 N., R. 1 W.
S. L. B. & M.
SOUTH OGDEN CITY, WEBER COUNTY

SURVEY DATE: 5-13-92

RECEIVED

AUG 31 1992

Weber County Surveyors