





DESCRIPTION

Warranty Deed, Executed August 1, 1961, Recorded October 3, 1961

Entry No. 365552, Book 690, Pages 650-655 Grantor: Weber Basin Water Conservancy District

Grantee: United States of America

A tract of land in the Northwest Quarter of the Northwest Quarter ( $NW_{4}^{1}NW_{4}^{1}$ ) of Section Twenty-three (23), Township Five (5) North, Range One (1) West, Salt Lake Base and Meridian, being more particularly described as follows: Beginning at a point on the centerline of what is known as the Weber Aqueduct P2.8R Discharge Line at Station 20+94.7, a point on the centerline of the County Road, from which point the Northwest corner of said Section 23 bears North 51°46'

West Eight Hundred Eighty-nine and Two-tenths (889.2) feet, and running thence North 69°49' West along the center of said County road Sixty-three and Six-tenths (63.6) feet; thence North 39°27' East One Hundred Ninety-two and Three-tenths (192.3) feet; thence North 3°55' East One Hundred Fifty-four and Nine-tenths (154.9) feet;

thence North 39°27' East Seventy-six (76.0) feet;

thence South 80°16' East One Hundred Forty-seven and Three-tenths (147.3) feet; thence South 50°33' East Twenty-two (22.0) feet to Station 25+41.0 of said Diascharge Line, from which point from which point the Northwest corner of said Section 23 bears North 78°10' West Nine Hundred Ninety-nine and Nine (999.9)

thence continuing South 50°33' East Fifteen (15.0) feet; thence South 39°27' West Sixty-one (61.0) feet;

thence South 5°33' East Five (5.0) feet;

feet to a point in the center of said County Road;

thence North 69°49' West along the center of said road Twenty-one and Two-tenths

Bureau of Reclamation and Weber Basin Water Conservancy District for the purpose of marking on the ground the boundaries of the parcel of land shown hereon in preparation for fencing said boundaries.

Weber Basin Water Conservancy District as the plaintiff. See Final Judgement of at Pages 353-359 in the office of the Weber County Recorder. The property was subsequently conveyed to the United States Of America under management of the United States Department of the Interior, Bureau of Reclamation.

Combe, making it the senior parcel in the area. The parcel adjoining easterly was created in November 1963 and has since been combined with its parent parcel. The parcel adjoining westerly, Parcel No. 07-086-0014, was created in December 1964 and has retained its original description. Parcel No. 07-086-0014 has been surveyed by Reeve & Associates, Inc. See the record of survey plat filed September 16, 2021 with the Weber County Surveyor's office as file no. 6977. This survey agrees with record data along its' common boundary with the Reclamation parcel. The only minor conflicts between the Reclamation parcel description and the adjoining parcel descriptions are the result of obvious errors in the adjoining parcel's descriptions. A previous survey of the Reclamation parcel, apparently performed by Reclamation employees, placed property corner monuments in error as shown hereon. No record has been found of this survey, therefore no explanation exists of how the property corner determinations were made. After consultation with Kriss Dow and Lance Youngberg, adjacent property owners, I concluded to place boundary monuments according to the bearings and distances found in the original Warranty Deed description received by the United States in 1961, as shown hereon.

The Northwest Corner of Section 23 is currently marked with a brass monument dated 1960. Information obtained from the Weber County Surveyor indicates that the existing monument replaced a previous stone monument in the same location. This suggests that the monument in place today is the monument referred to in the description of the Reclamation parcel recorded in 1961 as the Northwest Corner of Section 23. For lack of any evidence to the contrary and in agreement with the relied upon the Utah State Plane, North Zone for its bearing base.

(21.2')

MAR 17 2023

FILE # 7508

I, Nolan C. Hathcock, a Professional Land Surveyor licensed under Title 58, Chapter 22, Professional Engineers and Professional Land Surveyors Licensing Act, holding license No. 166346, do hereby certify that this plat represents the results of a survey performed by me and that the information shown hereon is true and correct to the best of my knowledge and belief.