

# **RECORD BOUNDARY DESCRIPTION (11-033-0083)**

A PART OF THE SOUTHWEST QUARTER OF SECTION 5, TOWNSHIP 6 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN, MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGINNING AT A POINT ON THE SOUTHERLY RIGHT-OF-WAY LINE OF 1100 NORTH STREET BEING LOCATED NORTH 88°56'46" WEST 255.82 FEET ALONG THE SOUTH LINE OF SAID SOUTHWEST QUARTER AND SOUTH 0°00'00" EAST 31.48 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION 5; RUNNING THENCE SOUTH 2°01'59" EAST 97.63 FEET; THENCE SOUTH 13°07'46" EAST 125.35 FEET; THENCE ALONG THE ARC OF A 57.62 RADIUS FOOT CURVE TO THE LEFT 41.35 FEET, HAVING A CENTRAL ANGLE OF 41°06'59" WITH A CHORD BEARING SOUTH 29°49'55" EAST 40.47 FEET; THENCE ALONG THE ARC OF A 143.14 FOOT RADIUS CURVE TO THE LEFT 46.29 FEET, HAVING A CENTRAL ANGLE OF 18°31'47" WITH A CHORD BEARING SOUTH 79°17'52" EAST 46.09 FEET; THENCE NORTH 88°44'34" EAST 112.68 FEET; THENCE ALONG THE ARC OF A 50.00 FOOT RADIUS CURVE TO THE LEFT 46.41 FEET, HAVING A CENTRAL ANGLE OF 53°10'55" WITH A CHORD BEARING SOUTH 63°34'41" EAST 44.76 FEET TO THE WESTERLY BOUNDARY LINE OF THOROUGHBRED MEADOWS 1ST AMENDMENT; THENCE ALONG SAID WESTERLY BOUNDARY LINE FOLLOWING TWO(2) COURSES: (1) SOUTH 1°08'50" WEST 57.73 FEET: (2) SOUTH 1°44'24" WEST 280.49 FEET: THENCE SOUTH 74°30'12" WEST 381.20 FEET; THENCE NORTH 22°51'38" WEST 600.14 FEET; THENCE NORTH 3°49'18" WEST 84.00 FEET TO A POINT ON THE EASTERLY BOUNDARY LINE OF ROCKING R SUBDIVISION PHASE 2: THENCE ALONG SAID EASTERLY LINE NORTH 1°20'37" WEST 97.22 FEET TO THE SOUTHERLY RIGHT-OF-WAY LINE OF 1100 NORTH STREET; THENCE ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE FOLLOWING THREE(3) COURSES; (1) NORTH 89°18'37" EAST 185.68 FEET; (2) ALONG THE ARC OF A 282.00 FOOT RADIUS CURVE TO THE RIGHT 31.39 FEET, HAVING A CENTRAL ANGLE OF 6°22'39" WITH A CHORD BEARING SOUTH 87°39'19" EAST 31.37 FEET; (3) SOUTH 84°28'00" EAST 151.63 FEET TO THE POINT OF BEGINNING. CONTAINING 297,044 SQUARE FEET OR 6.819 ACRES MORE OR LESS.

## ADJUSTED BOUNDARY DESCRIPTION (11-033-0083)

A PART OF THE SOUTHWEST QUARTER OF SECTION 5, TOWNSHIP 6 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN. MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT ON THE SOUTHERLY RIGHT-OF-WAY LINE OF 1100 NORTH STREET BEING LOCATED NORTH 88°56'46" WEST 271.86 FEET ALONG THE SOUTH LINE OF SAID SOUTHWEST QUARTER AND SOUTH 0°00'00" EAST 30.23 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION 5; RUNNING THENCE SOUTH 2°03'28" EAST 99.77 FEET; THENCE NORTH 87°54'21"EAST 15.93 FEET; THENCE SOUTH 13°07'46" EAST 125.35 FEET; THENCE ALONG THE ARC OF A 57.62 RADIUS FOOT CURVE TO THE LEFT 41.35 FEET, HAVING A CENTRAL ANGLE OF 41°06'59" WITH A CHORD BEARING SOUTH 29°49'55" EAST 40.47 FEET: THENCE ALONG THE ARC OF A 143.14 FOOT RADIUS CURVE TO THE LEFT 46.29 FEET, HAVING A CENTRAL ANGLE OF 18°31'47" WITH A CHORD BEARING SOUTH 79°17'52" EAST 46.09 FEET; THENCE NORTH 88°44'34" EAST 112.68 FEET; THENCE ALONG THE ARC OF A 50.00 FOOT RADIUS CURVE TO THE LEFT 46.41 FEET, HAVING A CENTRAL ANGLE OF 53°10'55" WITH A CHORD BEARING SOUTH 63°34'41" EAST 44.76 FEET TO THE WESTERLY BOUNDARY LINE OF THOROUGHBRED MEADOWS 1ST AMENDMENT; THENCE ALONG SAID WESTERLY BOUNDARY LINE FOLLOWING TWO(2) COURSES; (1) SOUTH 1°08'50" WEST 57.73 FEET; (2) SOUTH 1°44'27" WEST 280.14 FEET; THENCE SOUTH 74°30'12" WEST 381.20 FEET; THENCE NORTH 22°51'38" WEST 600.14 FEET; THENCE NORTH 3°49'18" WEST 84.00 FEET TO A POINT ON THE EASTERLY BOUNDARY LINE OF ROCKING R SUBDIVISION PHASE 2; THENCE ALONG SAID EASTERLY LINE NORTH 1°20'37" WEST 97.22 FEET TO THE SOUTHERLY RIGHT-OF-WAY LINE OF 1100 NORTH STREET; THENCE ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE FOLLOWING THREE(3) COURSES; (1) NORTH 89°18'37" EAST 185.68 FEET; (2) ALONG THE ARC OF A 282.00 FOOT RADIUS CURVE TO THE RIGHT 31.39 FEET, HAVING A CENTRAL ANGLE OF 6°22'39" WITH A CHORD BEARING SOUTH 87°39'19" EAST 31.37 FEET; (3) SOUTH 84°28'00" EAST 135.52 FEET TO THE POINT OF BEGINNING. CONTAINING 295,293 SQUARE FEET OR 6.779 ACRES MORE OR LESS.

### **RECORD BOUNDARY DESCRIPTION (11-033-0082)**

PART OF THE SOUTHWEST QUARTER OF SECTION 5, TOWNSHIP 6 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN, MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGINNING AT A POINT ON THE SOUTHERLY RIGHT-OF-WAY LINE OF 1100 NORTH STREET BEING LOCATED NORTH 88°56'46" WEST 255.82 FEET ALONG THE SOUTH LINE OF SAID SOUTHWEST QUARTER AND SOUTH 0°00'00" EAST 31.48 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION 5; RUNNING THENCE ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE FOLLOWING THREE(3) COURSES: (1) SOUTH 84°28'00" EAST 43.83 FEET; (2) ALONG THE ARC OF A 348.00 FOOT RADIUS CURVE TO THE LEFT 32.20 FEET, HAVING A CENTRAL ANGLE OF 5°18'04" WITH A CHORD BEARING SOUTH 87°07'02" EAST 32.19 FEET (3) SOUTH 89°46'04' EAST 179.81 FEET TO THE WESTERLY BOUNDARY LINE OF THOROUGHBRED MEADOWS 1ST AMENDMENT: THENCE ALONG SAID WESTERLY BOUNDARY LINE SOUTH 1°08'49" WEST 223.24 FEET; THENCE SOUTH 90°00'00" WEST 51.00 FEET; THENCE ALONG THE ARC OF A 50.00 FOOT RADIUS CURVE TO THE RIGHT 33.21 FEET, HAVING A CENTRAL ANGLE OF 40°23'42" WITH A CHORD BEARING SOUTH 17°39'36" EAST 32.60 FEET; THENCE SOUTH 88°44'34" WEST 112.68 FEET; THENCE ALONG THE ARC OF A 46.29 FOOT RADIUS CURVE TO THE RIGHT 46.29 FEET, HAVING A CENTRAL ANGLE OF 18°31'47" WITH A CHORD BEARING NORTH 79°17'52" WEST 46.09 FEET; THENCE ALONG THE ARC OF A 57.62 FOOT RADIUS CURVE TO THE RIGHT 41.35 FEET, HAVING A CENTRAL ANGLE OF 41°06'59" WITH A CHORD BEARING NORTH 29°49'55" WEST 40.47 FEET; THENCE NORTH 13°07'46" WEST 125.35 FEET; THENCE NORTH 2°01'59" WEST 97.63 FEET TO THE POINT OF BEGINNING. CONTAINING 59,252 SQUARE FEET OR 1.360 ACRES MORE OR LESS.

#### ADJUSTED BOUNDARY DESCRIPTION (11-033-0082)

A PART OF THE SOUTHWEST QUARTER OF SECTION 5, TOWNSHIP 6 NORTH, RANGE 1 WEST OF THE SALT ✓ LAKE BASE AND MERIDIAN, MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGINNING AT A POINT ON THE SOUTHERLY RIGHT-OF-WAY LINE OF 1100 NORTH STREET BEING LOCATED NORTH 88°56'46" WEST 271.86 FEET ALONG THE SOUTH LINE OF SAID SOUTHWEST QUARTER AND SOUTH 0°00'00" EAST 30.23 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION 5; RUNNING THENCE ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE FOLLOWING THREE(3) COURSES; (1) SOUTH 84°28'00" EAST 59.94 FEET; (2) ALONG THE ARC OF A 348.00 FOOT RADIUS CURVE TO THE LEFT 32.20 FEET, HAVING A CENTRAL ANGLE OF 5°18'04" WITH A CHORD BEARING SOUTH 87°07'02" EAST 32.19 FEET (3) SOUTH 89°46'04" EAST 179.81 FEET TO THE WESTERLY BOUNDARY LINE OF THOROUGHBRED MEADOWS 1ST AMENDMENT; THENCE ALONG SAID WESTERLY BOUNDARY LINE SOUTH 1°08'49" WEST 223.24 FEET; THENCE SOUTH 90°00'00" WEST 51.00 FEET; THENCE ALONG THE ARC OF A 50.00 FOOT RADIUS CURVE TO THE RIGHT 33.21 FEET, HAVING A CENTRAL ANGLE OF 38°03'21" WITH A CHORD BEARING SOUTH 17°39'36" EAST 32.60 FEET; THENCE SOUTH 88°44'34" WEST 112.68 FEET: THENCE ALONG THE ARC OF A 46.29 FOOT RADIUS CURVE TO THE RIGHT 46.29 FEET, HAVING A CENTRAL ANGLE OF 18°31'47" WITH A CHORD BEARING NORTH 79°17'52" WEST 46.09 FEET: THENCE ALONG THE ARC OF A 57.62 FOOT RADIUS CURVE TO THE RIGHT 41.35 FEET. HAVING A CENTRAL ANGLE OF 41°06'59" WITH A CHORD BEARING NORTH 29°49'55" WEST 40.47 FEET: THENCE NORTH 13°07'46" WEST 125.35 FEET: THENCE SOUTH 87°54'21" WEST 15.93 FEET: THENCE NORTH 2°03'28" WEST 99.77 FEET TO THE POINT OF BEGINNING. CONTAINING 60,825 SQUARE FEET OR 1.396 ACRES MORE OR LESS.

#### ADJUSTMENT AREA BOUNDARY DESCRIPTION

A PART OF THE SOUTHWEST QUARTER OF SECTION 5, TOWNSHIP 6 NORTH, RANGE 1 WEST OF THE SALT LAKE BASE AND MERIDIAN, MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGINNING AT A POINT ON THE SOUTHERLY RIGHT-OF-WAY LINE OF 1100 NORTH STREET BEING LOCATED NORTH 88°56'46" WEST 271.86 FEET ALONG THE SOUTH LINE OF SAID SOUTHWEST QUARTER AND SOUTH 0°00'00" EAST 30.23 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION 5; RUNNING THENCE ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE SOUTH 84°28'00" EAST 16.11 FEET; THENCE SOUTH 02°01'59" EAST 97.63 FEET; THENCE SOUTH 87°54'21" WEST 15.93 FEET; THENCE NORTH 02°03"28" WEST 99.77 FEET TO THE POINT OF BEGINNING. CONTAINING 1574.14 SQUARE FEET MORE OR LESS.

#### NARRATIVE

THE PURPOSE OF THIS SURVEY WAS TO ADJUST AND ESTABLISH THE BOUNDARIES OF THE SHOWN PARCELS AND SET THE PROPERTY CORNERS OF THE PARCELS AS SHOWN AND DESCRIBED HEREON. THE SURVEY WAS ORDERED BY HEIDI WAHLEN. THE BASIS OF BEARING IS THE SOUTH LINE OF SECTION 5, TOWNSHIP 6 NORTH, RANGE 1 WEST, OF THE SALT LAKE BASE AND MERIDIAN WHICH BEARS NORTH 88°56'46" WEST, WEBER COUNTY, UTAH NORTH NAD 83 STATE PLANE GRID BEARING. THE WARRANTY DEED(S) RECORDED AS ENTRY NUMBER 2677864 AND 2901338 ALONG WITH DEEDS OF ADJOINING PROPERTY OWNERS WERE USED TO ESTABLISH PROPERTY BOUNDARIES. BOUNDARIES WERE ALSO DETERMINED BY THE FOUND MONUMENTS AS SHOWN AND DESCRIBED HEREON.

LEGEND					
WEBER COUNTY MONUMENT AS NOTED					
O SET 24" REBAR AND CAP MARKED GARDNER ENGINEERING					
SUBJECT PROPERTY BOUNDARY LINE					
ADJACENT PARCEL	0'	20'	40'	80'	120'
SECTION LINE					
EASEMENT	Scale in Feet 1" = 40'				



