



SURVEYORS CERTIFICATE

I, Larry M. Buttars, a registered Civil Surveyor as prescribed by the laws of the State of Utah and hold License No. 2594 do hereby certify that I made a survey of the above described property in this Plat hereon a true and correct representation of said survey.

Date 11-17-92 Sgn *Larry M. Buttars*

DESCRIPTION

Part of lots 9 and 10, Block 4, Plat A, Ogden City Survey Beginning at the Southeast Corner of said lot 10 and running thence N 0° 58' E 91.00 ft, thence N 89° 02' W 132.66 ft, to the West line of Lot 10, thence N 0° 58' E 33.00 ft, thence N 89° 02' W 66.33 ft, thence S 0° 58' W 124.00 ft, thence S 89° 02' E 198.99 ft to the point of beginning Cont. 20,291 sq ft

NARRATIVE

Staked West two corners only surveyed for the purpose of constructing retaining wall. Ogden City bearings and Survey Monuments were used for this survey.

LEGEND

- o Set 3/4" x 24 re bar with plastic stamped L Buttars R L 2594
- Set PK nail with ribbon

RECEIVED
JUN 28 1993

BUTTARS SURVEYING 1815 26 TH STREET OGDEN, UT 84401 PHONE 392-5291	
CLIENT WADMAN CONST	
SURVEY LOCATION LOTS 9 & 10, PLATA, OGDEN CITY SURVEY PART OF NE 1/4 SEC 32 T 6 N, R 1 W	
SURVEY DATE 11-16-92	